

AD-A036 828

ARMY ENGINEER DISTRICT ST LOUIS MO

F/G 8/6

COMMENTS ON ADVANCE COPY OF SUMMARY REPORT ON MERAMEC RIVER, MI--ETC(U)
JUL 65

UNCLASSIFIED

NL

1 OF 1
AD
A036828



END

DATE

FILMED

4-77

U.S. Army Engineer District, St. Louis, Mo.
~~Corps of Engineers~~
St. Louis, Missouri

401538

ENGBR

23 July 1965

SUBJECT: Comments on Advance Copy of Summary Report on Meramec River, Missouri, Comprehensive Basin Study,

MEMORANDUM FOR RECORD:

11 23 Jul 65 12 79p

ADA 036828

1. A preliminary review of subject report has raised a number of questions on which additional information or clarification is required. These are discussed in the following paragraphs.

2. Reference is made to letter of 24 November 1964, on subject report, in which it is stated that "The Board decided to return the report to the District to await receipt of the official report of the Public Health Service from the U. S. Department of Health, Education, and Welfare, relating to the potential needs and value of water storage for municipal, industrial and quality control purposes." A report prepared by HEW Public Health Service, Region VI, Kansas City, Missouri, December 1964, has been included as Attachment 1 on the subject summary report. However, it is understood that HEW, Washington, has not yet given its approval to the field report.

3. Attachment 2, on the summary report, presents a derivation of water supply and water quality control requirements prepared by the Corps of Engineers and stated to be based on data and information furnished informally by the U. S. Public Health Service. However the water supply and water quality demands developed by the Corps are somewhat larger than values shown in the HEW field report. Both reports state that the only area in the basin where there is a need for low-flow augmentation in the interest of water supply, is in the lower Meramec River basin area-Reach M-7. The HEW report states that the withdrawal of ground water in the upper areas may be increased to 280 million gallons per day without depletion of the aquifer. Since the need for water quality in the upper basin prior to 2020 is about 70 m.g.d., as indicated by HEW, consideration might be given to the use of this ground water as the need develops, as an alternative supplementary source for water quality control in the upper basin.

CO AVAILABLE TO DDC DOES NOT
PERMIT FULLY LEGIBLE PRODUCTION

401538

DDC
RECEIVED
MAR 14 1977
REGISTRY

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

ENGBR

23 July 1965

SUBJECT: Comments on Advance Copy of Summary Report on Meramec River, Missouri, Comprehensive Basin Study

4. The HEW report, page VIII-13, states that the most likely alternative to providing reservoir storage for water quality control above Reach M-7, was found to be pumping part of the treated wastes 19 miles to the Mississippi River where sufficient flow is available to satisfactorily assimilate the treated wastes. The annual value of 342,000 acre feet of demand on storage for quality control regulation is given as the annual transmission cost of the treated waste to the Mississippi River which is \$261,000. The Corps report allocates a maximum of 191,000 acre-feet of storage for water quality control in the three large reservoirs, Meramec Park, Union, and Pine Ford, for which the allocated total annual cost is \$356,200. See Tables 5 and 14 of summary report. It appears that the alternative is less costly and water quality storage as proposed for these reservoirs is not economically justified.

5. Table 7, attachment 2, indicates that the storage deficiency for water supply only, --based on the assumption that the treated M-7 wastes are pumped 19 miles to the Mississippi River, --would be 167,051 acre-feet for sub-basin M-7, to meet the 2070 needs. The Corps report provides for more than 430,000 acre-feet of water supply storage by 2070, because of the sharing of recharge or streamflow with the needs for water quality control reservoir storage. It appears that the difference in costs between the 167,000 acre-feet and the 430,000 acre-feet of water supply storage plus corresponding evaporation losses might be credited to the alternative of pumping the treated M-7 wastes to the Mississippi River.

6. On the basis of the above paragraph on pumping to the Mississippi River the reservoir storage of 332,000 acre feet in the Meramec Park project, now allocated to water supply and water quality, would be more than adequate to serve the entire water supply needs in the M-7 basin area until after the year 2070. Accordingly, on this basis reservoir storage reduction would be practical for the following:

SEARCHED	INDEXED	SERIALIZED	FILED
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
JUL 23 1965			
FBI - ST. LOUIS			
A			

ENGBR

23 July 1965

SUBJECT: Comments on Advance Copy of Summary Report on Meramec River, Missouri, Comprehensive Basin Study

<u>Project</u>	<u>Storage given in report</u>	<u>Estimated storage needed as revised above</u>
	<u>acre-feet</u>	<u>acre-feet</u>
Irondale	161,000	44,500
Pine Ford	285,000	220,000
Union	<u>528,000</u>	<u>383,000</u>
Total	974,000	647,500

7. Table 5, page 24, of summary report shows that the storage allocated to local water quality control for I-38 reservoir is 2,500 acre feet and the corresponding allocated average annual cost is \$132,900. The HEW field report, on Exhibit 12, attachment 1, gives benefits for water quality control in reaches B-1, B-2, and B-3 as \$73,600 annually based on 14,900 acre feet draft on storage from a single purpose reservoir developed at the I-38 reservoir site. The Corps project indicates storage for quality water control developed at a first cost of \$2,643,000/2,500 or \$1,060 per acre-foot, and HEW indicates storage for water quality control developed at a cost of \$4,200,000/14,900 or \$280 per acre-foot, which discounted at 3 percent from 1990 to 1970 is \$2,326,000/14,900 or \$156 per acre-foot. It appears that the alternative project for water quality control is less costly than when storage is included in I-38, and therefore water quality storage should not be included in this multiple-purpose project. A project for flood control and recreation only at this site appears to be not economically feasible at this time. Additional data in this regard is needed.

8. As indicated in paragraph 6 above the capacity of the Irondale project should be reduced from 161,000 acre feet to 44,500 acre feet. Since the conservation and recreational water surface areas would become smaller by the revised formulated project the recreational costs and benefits should be adjusted accordingly. Based on maximum surface area of the conservation pool, the revised recreation benefits apparently will become about one-quarter the value proposed for the original project. Furthermore under PL 89-72, dated 9 July 1965, the "Federal Water Project Recreation Act," the average annual charges allocated to recreation should not exceed one-half the total average annual cost. The

ENGBR

23 July 1965

SUBJECT: Comments on Advance Copy of Summary Report on Meramec River, Missouri, Comprehensive Basin Study

Irondale project proposed in the summary report has a ratio of average annual charges for recreation to total project average annual charges of \$426,900/\$670,200 or about 0.64. Therefore on this basis alone, the project should be reformulated.

9. Reduction in reservoir storage capacities for both Union and Pine Ford projects as discussed in paragraph 6 above, apparently would result in costs for recreation in conflict with the Federal Water Project Recreation Act. Consideration should be given to modification of the storage capacities and appropriate changes in recreation features and costs.

10. The District Engineer, on page 54, paragraph 39d(1) recommends non-Federal interests give assurances that they will repay the costs allocated to water supply, etc. Costs of water supply storage to meet the needs over the first 50 years of the period of analysis are presently estimated at \$761,000 for construction and \$3,700 annually for maintenance, operation, and major replacements. Costs of water supply to meet the needs covering the last 50 years of the period of analysis are currently estimated at \$8,283,000 for construction, etc. It might be understood from this statement that for the water needed the last 50 years, there should be no charge for interest on the preceding 50 years. See paragraphs 29 and 36 of summary report. However, assuming a 10 year interest free period on future water supply the interest on the \$8,283,000 compounded over the interim 40-year period alone would amount to 242 percent of the basic amount or roughly \$20 million. Therefore future water supply 50 years hence should cost local interests at least \$28 million. However, if the future water supply is omitted from the project formulation a comparable amount of water quality storage should likewise be omitted. The Water Supply Act of 1958, provides that modification of a reservoir project heretofore authorized, surveyed, planned, or constructed to include storage as provided, which would seriously affect the purposes for which the project was authorized, surveyed, planned, or constructed, or which would involve major structural or operational changes shall be made only upon the approval of Congress as now provided by law. Furthermore, if water supply and water quality control storage for the second 50-year period is not included in the project formulation and the storage capacity is not changed, the storage corresponding to the future use for the above two purposes should be allocated to specific use for recreation. This storage would then become part of the separable costs to recreation and the costs should be shared

ENGBR

23 July 1965

SUBJECT: Comments on Advance Copy of Summary Report on Meramec River, Missouri, Comprehensive Basin Study

by local interests. After the local interests have contracted to pay their share for recreation there appears to be a question whether they would later allow the storage for recreation to be converted to storage for water supply and water quality control.

11. Table 8, attachment 5, provides a cost allocation for #17 Meramec Park Reservoir. However it is not possible to determine how the reservoir storage allocation and conversion on Table 7, attachment 5, affects the costs and benefits for water supply, water quality and recreation, as shown in Table 8, for each 25-year period as the conversions are made. Copies of cost allocations, corresponding to Table 8, should also be furnished for the information of the Boards staff for the other 4 major reservoirs recommended.

12. On the basis of allocation of costs for reservoirs shown on Table 9, attachment 5, the cost per acre-foot of storage allocated to water quality varies from \$1,060 for I-38, to about \$37 for Meramec Park, --and the cost per acre-foot allocated to water supply varies from \$43 for Pine Ford to \$1.50 for Irondale. The wide difference in cost between water quality storage and water supply storage is apparently due to the values based on the least costly alternative from which benefits are derived, and the discounting of values from the time that the needs should be met. In this connection attention is invited to Exhibit 13, attachment 1, HEW report. By programming construction for a sewage plant effluent pumping system in stages in 1990, 2020, and 2050, the construction cost was discounted from \$26,300,000 for first cost of construction to ~~\$14,512,666~~ for construction as the need develops. It is apparent that delaying construction of certain reservoirs on an equivalent basis to serve the water quality needs and also the water supply needs would result in more favorable benefits and a greater benefit-cost ratio for the system as a whole.

13. Table 2, attachment 5, cost estimates, angler-use sites, indicates that all lands and damages will be at Federal cost. This appears to conflict with ER 1165-2-4, 12 January 1965, Recreational Developments at non-Reservoir Projects. It is suggested that the cost estimates for the angler-use sites be made in accordance with the ER and data furnished for the Board.

COMMENTS
ON
BERH MEMORANDUM FOR RECORD
(SUMMARY REPORT - MERAMEC RIVER, MISSOURI)

The following information is furnished on views and comments contained in Memorandum for Record inclosed with letter, ENGBR, Board of Engineers for Rivers and Harbors, 27 July 1965, subject: Meramec River, Missouri, Summary Report. References below refer to paragraphs in the Memorandum.

a. Reference paragraph 2 - official report of the Public Health Service. Report of the Public Health Service, dated December 1964, was officially approved by the Chairman of the Review Board for Water Supply and Pollution Control, Department of Health, Education, and Welfare, Washington, D. C., in February 1965. This was reconfirmed in telephone conversation on 28 July 1965 with representative of the Public Health Service, Region VI, Kansas City, Missouri, who was charged with the preparation of the report.

b. Reference paragraph 3 - derivation of water supply and water quality control requirements. In the derivation of water supply and water quality control requirements, the District used seasonal demands for both water supply and water quality control furnished by the Public Health Service. The difference in storage requirements determined by the Public Health Service and the Corps is reflected in the method of analysis. The Rainwater method used by the Public Health Service indicates draft-on-storage, which is the sum of the incremental excesses of needed releases over inflow during a climatic year, whereas the Corps analysis indicates storage requirements needed to meet demands over critical periods of record. For a fuller understanding of the Public Health Service analysis, there is attached as inclosure 1 a copy of critique on the Rainwater method. With regard to water quality in the upper basin area, the Public Health Service considered the use of groundwater as an alternative source, but found that the capital cost of the wells, which would require aerators and pumps, was higher than the capital cost of single-purpose reservoirs to supply the needed quality control water (see page VIII-9, Public Health Service report, dated December 1964).

c. Reference paragraph 4 - least costly alternative for water quality above Reach M-7. The annual value of \$261,000 estimated by the Public Health Service was based on the summation of costs for incremental pumping requirements to handle the waste loadings which exceed the assimilative capacity of the unregulated stream flows, Q_i . Pumping requirements reflect monthly variations in the assimilative capacity of the unregulated stream flow that theoretically would be exceeded 95 percent of the time, as determined by the Rainwater method. The value for Q_i used by the Public Health Service exceeds the corresponding unregulated flow as computed by the Corps of Engineers on a statistical basis by 40 to 58 percent for the summer season, 34 to 76 percent for the spring season, and an average of 35 percent for the winter season. From the foregoing, it is apparent that the use of the Rainwater method credits the unregulated stream flow, Q_i , in excess of the actual flows for the corresponding percent chance of occurrence. Reference is made to Table No. VIII-5, page VIII-13, Public Health Service report, which indicates that the summer season is critical in determining the benefits applicable to water quality control, whether based on dilution or pumping of waste. A reanalysis of the benefit evaluation was undertaken by the District based on the critical summer season. Since the unregulated flow, Q_i , for the summer season is approximately 50 percent too high, the amount of waste to be pumped would essentially have to be doubled. Basic cost data used by the Public Health Service in its evaluation are contained in letter dated 5 August 1965, inclosure 2. Pipeline costs, including applicable material and installation, were estimated to account for about 75 percent of the construction costs, the remaining 25 percent being the cost of the pumping station, including equipment. To handle the increased waste load, it would be necessary to increase the pipe size and double the capacity of the pump installations. Pipeline costs were increased 50 percent and the pumping station 100 percent. Assuming 80 percent of the operation and maintenance costs applicable to the cost of energy and 20 percent for materials in the pump station and maintenance of pipelines, energy costs were increased 100 percent and all other costs 20 percent. Based on the 3-1/8 percent interest rate and amortization over 100 years, discounted benefits applicable to the alternative of pumping are estimated at \$377,000 annually. This analysis is based on the same years of first need as indicated by the Public Health Service, which is in error since with lesser flow, time-of-needs would be advanced and the discounting effects would be less than indicated.

Based on the Corps procedures used in the Summary Report, the amount of pumping required during the critical low-flow periods of record would be greater than indicated in the above analysis. From the foregoing analysis, it is concluded that: (a) the least costly alternative for water quality control above Reach M-7 is single-purpose reservoirs, as used by the Corps, and (b) water quality storage provided in Meramec Park, Union, and Pine Ford Reservoirs is needed and economically justified.

d. Reference paragraph 5 - storage for water supply only. Table 7, Attachment 2, Summary Report, indicates that the storage deficiency for water supply alone would be 167,051 acre-feet for sub-basin M-7 to meet the 2070 needs. In order to avoid complete stream depletion, these requirements were analyzed over and above a selected base flow of 195 c. f. s., being the minimum flow of record in the lower basin area. Deficiency for water quality alone amounts to 393,725 acre-feet. When based on concurrent demands, the total deficiency for both water supply and quality control by the year 2070 becomes 1,180,568 acre-feet. The five reservoirs recommended for construction in the basin plan are capable of meeting all the water supply needs to the year 2070 and water quality needs to the year 2045 in the lower basin area. The adjusted amount of storage required is estimated at 430,092 acre-feet for water supply and 190,461 acre-feet for water quality control. All the foregoing figures exclude allowance for evaporation losses. Since the alternative of pumping treated wastes to the Mississippi River was found not to be the least costly alternative, as indicated in subparagraph c above, the difference in cost between 167,051 acre-feet and 430,092 acre-feet of water supply storage cannot be credited to this alternative.

e. Reference paragraph 6 - reservoir storage reduction, Irondale, Pine Ford, and Union. Since pumping of wastes to the Mississippi River was found not to be the least costly alternative, the storage provided in these three reservoirs is needed to serve water supply and water quality demands to the fullest extent practical in the lower basin area.

f. Reference paragraph 7 - cost of storage for water quality I-38 Reservoir. Draft-on-storage estimated at 14,900 acre-feet is based on reservoir releases for the year 2070, as shown in Table No. VIII-4, page VIII-12, of the Public Health Service report.

Storage of 2,500 acre-feet estimated by the Corps represents supplemental storage required during the first 50 years, or to the year 2020. To compare this figure with Public Health Service values, monthly releases for the year 2020 needs, as shown in Table No. VIII-4, were used. The total draft-on-storage based on these releases is estimated at 2,340 acre-feet. The size of a single-purpose reservoir to provide this draft-on-storage must include allowances for evaporation, as well as sedimentation. Using Corps estimates, approximately 1,855 acre-feet of storage would be required for evaporation and 4,715 acre-feet for 100-year sedimentation. Thus, the total storage required in a single-purpose reservoir amounts to 8,910 acre-feet to meet the year 2020 requirements. Table 2 of Attachment 4 to the Summary Report shows that 9,042 acre-feet of storage, having a reservoir cost of \$4,055,000, would be required for Reaches B-1 through B-3 to meet the year 2020 needs. Assuming a reservoir to meet the Public Health Service draft-on-storage of 2,340 acre-feet for the year 2020 to have a comparable cost of about \$4,000,000, the unit cost per acre-foot would be equal to approximately \$1,710. The Corps allocated unit cost for water quality of \$1,060 reflects a savings in project joint costs. Further reference is made to Table 5 of Attachment 2 to the Summary Report. Base storage requirements amounting to 17,215 acre-feet would be needed to meet the 2070 needs at Sullivan, which includes Reaches B-1 through B-3. To this are added evaporation requirements of 2,168 acre-feet and 4,715 acre-feet of storage for sedimentation. A single-purpose reservoir to meet the 2070 needs would require a total capacity of 24,098 acre-feet. Table 2 of Attachment 4 to the Summary Report shows that a reservoir having a storage capacity of 24,098 acre-feet would cost approximately \$4,705,000. The unit cost for the effective storage is estimated at \$273 per acre-foot (\$4,705,000 divided by 17,215 acre-feet). This compares with the \$280 per acre-foot cited by the Board. Attention is also invited to the fact that the annual charge of \$73,600, shown in Exhibit No. 12 of the Public Health Service report, is based on construction costs only and does not reflect annual charges for operation and maintenance, including replacements. From the foregoing analysis, it is concluded that project formulation, cost allocations, and benefit evaluations for Reservoir I-38 are correct and the reservoir is economically feasible.

g. Reference paragraph 8 - Irondale Reservoir. Since Irondale Reservoir as formulated in the Summary Report does not meet

the criterion outlined in Section 9 of the Federal Water Project Recreation Act, approved 9 July 1965, in that the sum of allocations to recreation and fish and wildlife enhancement exceeds the sum of allocations to other uses, a review of project formulation was undertaken. This reservoir was given a high priority by the Bureau of Outdoor Recreation. In reformulation, consideration was given to providing as large a normal water surface area as practical. The total joint-use storage was reduced by 21,000 acre-feet and the normal pool area 500 acres, from 4,600 to 4,100 acres. The top elevation of the dam was lowered three feet. The total cost of the project is currently estimated at \$12,900,000. Of the total reduction in first cost of \$1,500,000, \$137,000 is in the cost of recreation facilities based on a lesser water surface area and recreational lands and a reduction in visitor-day attendance. The project as reformulated would retain the benefits for flood control, water quality control, and navigation, whereas the water supply and recreation benefits would be reduced. The benefit-cost ratio for the project is estimated at 1.3 to 1.0 and meets the criterion of Section 9 of the Federal Water Project Recreation Act, having a ratio of first costs allocated to recreation and fish and wildlife enhancement to total project costs of 0.45 to 1. Pertinent data on the project as reformulated, including allocated costs and cost apportionment, are contained in inclosure 3.

h. Reference paragraph 9 - modification of storage capacities in Union and Pine Ford Reservoirs. As indicated in subparagraphs c and e, no storage reduction in these reservoirs is warranted. Furthermore, both projects as now formulated meet the criterion of Section 9 of the Federal Water Project Recreation Act.

i. Reference paragraph 10 - future water supply storage. The Summary Report, Table 16, shows costs to be repaid for water supply storage to be utilized in the first 50 years and the additional cost for storage to meet long-term needs during the second 50-year period. These estimates are based on the schedule of use as given in Table 5 of the Summary Report. Contractual agreements would be required for storage allocated to water supply to meet the demands for the first 50-year period. However, only assurances are required that demands for use of future storage would be made within a period of time which will permit paying out the costs allocated thereto within the life of the project. Since the storage for water supply to be used during

the second 50-year period is not dedicated initially, but converted from other interim uses, no interest charges should be required prior to time of conversion. Similar provisions are included in contracts between the United States and the City of Paris, Texas, for water storage space in Pat Mayse Reservoir, dated 14 January 1965, and between the United States and Trinity River Authority of Texas for water storage space in Bardwell Reservoir, dated 13 May 1963. Both of these contracts provide for reimbursement of costs allocated to initial water supply storage and only assurances for future water supply storage. Neither contract includes interest payment for future water supply prior to the time such storage is first used for that purpose. The Governor's Advisory Committee on Resurvey of the Meramec Basin expressed the opinion that provision for future water supply storage should be included in the comprehensive plan for development of the water resources of the basin. Enabling legislation enacted by the Legislature will permit the State to assume obligations for water supply storage in the reservoirs. To include provisions for water supply and water quality control requirements for the second 50-year period in the initial construction is more economical than it would be to fully or partially defer such provisions until the demand for such purposes arises. In the interim, this storage is used to the maximum extent practical for recreation, and local interests are paying a fair share for such use. In no case is the recreational reimbursement for specific storage, but rather a cash contribution for modifications to provide optimum recreation usage. There is no basis for storage ownership, but rather a sharing in costs in relation to applicable benefits, as reflected in project formulation. There is every reason to believe that the State accepts this premise and will sponsor and fulfill the requirements for local participation in recreation.

j. Reference paragraph 11 - cost allocations. Table 7 of Attachment 5 to the Summary Report reflects the phased supplemental storage required for water supply and water quality, as derived in Attachment 2; timing and supplemental storage requirements which were the bases for evaluation and discounting of benefits, as shown in Attachment 4; bases for benefits and applicable increments of costs used in the project formulation, as shown in Attachment 3; and blocks of storage used for determining dual cost aspects and applicable benefits for suballocations used in the reservoir cost allocations. Cost allocations for Pine Ford, Irondale (revised), Union, and I-38 Reservoirs are contained in inclosure 4.

k. Reference paragraph 12 - costs per acre-foot of storage.

The wide difference in cost between water quality storage and water supply storage is due to the values based on the least costly alternative from which the benefits were derived and discounting effects in relation to the time of need. The value of both water supply and water quality in the lower basin area, Reach M-7, was based on a single-purpose reservoir (Meramec Park), whose unit construction cost per acre-foot of storage is by far the cheapest in the basin. The benefits for these needs were then prorated to the individual reservoirs in relation to the storage provided. Since in all cases benefits for water quality governed in the cost allocations, the unit cost allocated to water quality in Reach M-7 proved to be far less than the unit cost allocated for water quality in the upper basin. Allocations of costs to recreation reflect the fact that the "other" cost aspect of the separable cost varies from a low of \$449 per surface acre for I-38 to \$1,670 per acre for Pine Ford. Surface acre was used as the unit measure of value since it is one of the more important criteria for recreational planning. Reservoir I-38, whose total joint-use storage is used within the first 50 years, carries the least applicable unit cost per surface acre for the "other" costs. Delaying construction of any of the reservoirs recommended for authorization in the Summary Report to serve the water supply and quality demands as the need arises would not be responsive to the basin needs, the dominant of which are flood control and recreation; would not provide for an equitable distribution of beneficial effects from the developments, both in time and geographic area; would unquestionably result in substantial overall increased costs; and would be locally unacceptable.

l. Reference paragraph 13 - cost estimates for angler-use sites. Cost estimates for angler-use sites have been reviewed in accordance with ER 1165-2-4, dated 12 January 1965. Estimates have been revised to show the cost of lands as a non-Federal responsibility. The total cost of the recreational development now provides for equal distribution of costs between Federal and non-Federal interests, as shown in inclosure 5.

m. Summary - general plan. In project formulation for the basin plan, consideration was given to a number of factors, the more significant of which are stated below:

(1) Basin needs are based on 100-year projections, 1970-2070.

(2) The dominant needs in the basin are flood control and recreation.

(3) Reservoir sites to satisfy major segments of the widespread needs are limited.

(4) Additional capacity to meet future needs is included initially in reservoirs where such can be accomplished at significant savings over subsequent enlargement.

(5) Storage requirements for water supply and water quality control are based on demands furnished by the Public Health Service.

(6) Draft-on-storage and the value of such storage furnished by the Public Health Service are not representative of operational requirements needed to meet the concurrent demands over the critical periods of record.

n. Conclusion. ^{Certain} Based on acceptance of the criteria cited in subparagraph m above, the general plan of basin development as proposed in the report is properly formulated, and will provide for the best use or combination of uses of water and related land resources to meet all foreseeable short- and long-term needs in the basin. Meramec Park, Union, Pine Ford, Irondale, and I-38 Reservoirs, proposed for authorization and construction, are required to meet the immediate demands in the Meramec River Basin at this time.

5 Incl

1. Rainwater critique
2. PHS ltr 5 Aug 65
3. Pertinent data -
Irondale Reservoir
4. Cost allocations -
reservoirs
5. Cost estimates -
angler-use sites

not included

CRITIQUE OF RAINWATER METHOD FOR EVALUATION OF WATER SUPPLY AND QUALITY CONTROL NEEDS

1. REFERENCES

- a. Staff paper prepared by Mr. Frank H. Rainwater, Physical Science Administrator, Technical Science Branch, Division of Water Supply and Pollution, Department of Health, Education, and Welfare, entitled "Hydraulic Facts Needed for Studies of Flow Regulations for Stream Quality Control," presented at a symposium on stream flow regulation for quality control at Cincinnati, Ohio, 3-5 April 1963.
- b. Paper prepared by Mr. Frank H. Rainwater, entitled "Hydrologic Aspects of Analysis of Flow Regulation Requirements for Quality Control."
- c. Report submitted by Region VI, Public Health Service, Kansas City, Missouri, entitled "Water Resources Study, Meramec River Basin, Missouri," dated February 1964. This study, since revised, indicated potential needs and value of water storage for municipal, industrial, and quality control purposes.

2. BACKGROUND

a. Critique of paper "Hydraulic Facts Needed for Studies of Flow Regulations for Stream Quality Control." The following points were presented in the paper:

(1) The hydraulic analysis for flow regulations study is a four-step procedure which:

(a) Describes the present annual stream flow and quality characteristics in terms of typical companion hydrographs having selected average recurrence intervals.

(b) Projects future stream flow and quality characteristics that would exist under projected water use and management in year(s) "X" without flow regulations.

(c) Computes the regulated stream flow regimen needed in year(s) "X" to meet the quality objectives.

(d) Schedules the flow regulation needs, including probable monthly distributions, over the life of the proposed structure.

(2) The responsibility involved in a flow regulation study is to control stream quality, not to maintain a stream flow. Hence, maintenance of a constant minimum stream flow is not the most efficient answer to quality control. Maximum regulation demands do not necessarily coincide in time with either minimum stream flows or maximum concentrations of pollutants. For example, the process of counteracting a BOD load imposed on a stream involves the oxygen concentration of receiving water, the reaction rate (deoxygenation), and reaeration factors - each of these is temperature sensitive. Hence, the stream flow requirement is dependent partially on temperature. In mineral quality control, the tons of mineral to be diluted may be less at minimum flow, or maximum concentrations, than at some higher flow. As is evident from the nature of the problem, its solution is approached through a chain of dependent sequential analytical treatments of facts and figures. Probably the most significant deficiency (knowledge) lies in the realm of interrelating water quality and stream flow. Stream quality and stream discharge are inseparable in these studies. For the purposes of analysis, each event in the past and future time series of events comprising stream behavior has two dimensions - quantity of flow and concurrent quality. One objective of flow regulation for quality control is satisfactory concentration of waterborne material. Knowledge of stream flow characteristics is of little use unless it can be associated closely with attendant stream qualities. With respect to stream flow alone, information available on the low-flow characteristics is weak in both national coverage and validity. Low flows are extremely sensitive to effects of geology, land use, and man's modification of the hydrologic regimen. Interstation correlation and regional analysis, so useful in flood frequency analysis, are only of limited use in low-flow studies. Time-of-travel data and velocity profiles of low-flow conditions are needed to route pollution loads, to position oxygen sags along the stream, and to predict sludge deposition and scour. Such data are virtually non-existent nationwide.

(It should be noted that in conjunction with the Meramec Basin Study, two reports undertaken by separate agencies were available for use in this phase of analysis. One was an "open-file report" prepared by the U. S. Geological Survey, Water Resource Division, Rolla, Missouri, on the Meramec River Basin. This was a low-water study covering the period 24 September through 1 October 1953. Because of existing drought conditions and apparent low-water discharges, a low-water study of the basin was made involving numerous discharge measurements and observations. The study was made for the following purposes: to better determine the distribution of the base flow in the basin; to determine

the gain or loss of water between various points in the basin; to compare the flow during this drought with the previous low flows of record at the gaging stations; and to have on record a better coverage concerning the low flows in the basin. The second study, prepared by the Missouri Water Pollution Board in 1963-64 contained detailed data from sampling stations established to determine the utilization of water resources; biological data; and bacteriological, chemical, physical, as well as flow information for the streams within the basin.)

(3) Since flow regulation studies are recognized as forecasts, statistical treatments of data are useful tools in a time series, such as historic stream flows. The size of the sample may be equated with the number of years of the record. In theory then, the longer the period of record, the better the estimate. In practice, this is not necessarily true because man is changing the statistical population from which the sample is drawn. Regulation, diversion, and increased consumptive use are continually changing the water quality regimen of streams. The water quality regimen responds to changes in flow regulation and also to man's use of water to transport wastes. Factors affecting changes are:

(a) Data obsolescence, the effects of which are particularly pronounced in low flows. This problem of obsolescence has several consequences in flow regulation studies. The hydrologists may be seriously misled by published low-flow frequency data compiled, unadjusted, from the historic record. Usually, such data require considerable reworking before they can be used with confidence.

(b) Stream depletion is another very important aspect of obsolescence. To fulfill its responsibility in making recommendations to the Federal construction agencies, the Public Health Service must base its analysis of regulation needs on future depleted or modified stream flows. The flow to be augmented 20 or 50 years hence will not be the same flow measured now, but rather a stream depleted by the existing water use and management. What is needed are accurate projections of depletion and other modifications. Regardless of the nature of the consumptive user, 30 to 40 percent of the water withdrawn in the United States is lost from the supply. No stretch of the imagination is required to see that future depletions will make increasing inroads on the static available supply.

b. Critique of paper "Hydrologic Aspects of Analysis of Flow Regulation Requirements for Quality Control." This paper outlines the approach to approximate "present and projected needs for stream flow regulation (draft-on-storage) for quality control independent of other proposed, predicted, and as yet unestablished or authorized uses of stream and reservoir storage." The following points were made:

(1) Mr. Rainwater's analytical method is designed to answer three questions:

(a) To establish the need and the amount of water releases from the reservoir for stream quality control.

(b) To establish if the flow at the reservoir site (and load center) is equal or exceeds the necessary releases, or whether draft-on-storage (stream flow regulation) is required to meet the necessary releases.

(c) If draft-on-storage is needed, how much water is to be stored each year for quality control.

(2) The analytical procedure is divided into four steps:

(a) Describe the base system in terms of quality and stream flow. This base system reflects the effects of existing and authorized water uses, permissible waste loadings, and flow modifications.

(b) Superimpose projected increases in waste loadings, water uses, depletions, etc., to change the stream quality and/or flow of the base system. The projected systems are described in terms of quality and stream flow.

(c) Compute the reservoir releases and net draft-on-storage as required to modify the projected system to meet the quality criteria.

(d) Adjust net draft-on-storage as required to compensate for problems of synchronization of releases and downstream needs and conveyance losses. This suggested regulation is termed recommended annual draft-on-storage.

(3) Establishment of the base system involves establishing a network of flow and quality conditions without flow regulation for quality control. It includes establishing in logical downstream sequence the hydrologic and established or authorized water use and management components affecting quality, and the locations in the system where stream deficiencies for quality control are to be computed. To compile quantity and quality data for the component of the base system, the analyst must draw a representative sample of the possible events that could occur. Although there are numerous ways of drawing such a sample, a convenient and effective way is to array unpredictable events by magnitude; divide them into a convenient number of strata (groups); and take the median of each group as representative of that group. Such a sample adequately describes the array of probable events, and each item in the sample has an equal chance of occurrence in any one year. Usually, five strata will suffice, with their respective median taken as the event having exceedence probabilities of 0.1, 0.3, 0.5, 0.7, and 0.9. The procedure is as follows:

(a) As a first step, low-flow frequency graphs of annual mean stream flows at the critical points in the study area are constructed. Annual means based on climatic year (April-March) are a little better for regulation studies than annual water-year means (October-September).

(b) Typical monthly distribution of annual uncontrolled runoff is determined. The suggested procedure involves selecting a gaging station that has a reasonably long-term record and is representative of the area under study; establish the median monthly flow for each month; and compute the distribution of median monthly means as a ratio to annual mean flows.

(c) Determine the necessary quality and stream flow inputs to the base system.

(d) Assemble the data on projected increases in waste loading, stream depletions, etc., over and above those reflected in the base system.

(e) Compute the necessary base system flow and quality data for critical points.

(f) Project flow and quality needs at the critical points.

(g) Determine reservoir releases to meet quality needs at critical periods.

(h) Compute draft-on-storage required ($\Delta_s = Q_o - Q_i$).

(4) In his discussion, Mr. Rainwater claims that presentation of stream flow regulation needs in terms of annual Δ_s has several desirable attributes. It gives the quantity of water needed in storage that should be available each year to control, when needed, stream quality. As such, it embodies the concept of "flow regulation for quality control, including monitoring and control mechanics in contrast to maintaining some prescribed flow regimen." Thus, in water-short areas, water would not be wasted by releases when not needed. The Δ_s and the attendant benefits can be moved by the construction agencies from one reservoir site to another having comparable quality of releases or divided among several reservoir sites. This knowledge of where and how much draft-on-storage is needed in the basin gives the construction agencies some flexibility and direction in developing future site studies.

3. EXPLANATION OF RAINWATER METHOD

The following is an explanation of the Rainwater method, as utilized by Region VI, Public Health Service, in its work for the St. Louis District study on Meramec River Basin, Missouri. The Public Health Service in its analysis first established the base system by dividing the basin into sub-basins that reflect hydraulic aspects and flow control. Sub-basins selected were:

a. Upper basin.

- (1) Big River Sub-basin.
- (2) Upper Meramec River Sub-basin.
- (3) Bourbeuse River Sub-basin.

b. Lower basin, which consisted solely of the lower portion of the Meramec River.

Each sub-basin was then divided into reaches of analysis and further broken down into load centers. These load centers were points that were selected to reflect sources of induced pollutants and were representative of selected population distribution centers. The present characteristics of the load centers were then defined in terms of population and water usage, expressed in terms of gallons per capita per

day. This gave a representation of the induced pollutant load that would have to be assimilated by the stream, assuming primary and secondary treatment in place. Projections were then made of the anticipated population growth in all parts of the basin on a time-phase basis. In conjunction with these population extrapolations, increased expected water use was also projected within the limits of the projections made by the U. S. Senate Select Committee. The product (population times water usage per capita) of these projections gave a basis for anticipated pollutant loads that were subsequently modified by anticipated mineral and organic pollutants to be anticipated from the industrial and rural aspects of the basin. To determine water quality requirements, the Public Health Service first determined the water supply (M&I) requirements and assumed that these demands were met and in place. The total water quality flow requirements (Q_t) were determined as the stream flow required to provide the necessary dilution to obtain a stream quality equal to 5 parts per million BOD. Its determination was based on the assumption that primary and secondary treatment had been provided the waste effluent at the discharge point or load centers. To determine the required stream flow (Q_o) necessary to meet the total flow requirements, the following formula was used: $Q_o = Q_t - Q_r$. Q_t was furnished on a seasonal basis, which recognized a temperature sensitive aspect, and was established in relation to water temperature. In the case of the Meramec Basin study, seasonal breakdowns were: a summer season of four months - June, July, August, and September; a spring and fall season of five months - March, April, May, October, and November; and a three-month winter season - December, January, and February. The return flow, Q_r , represents a portion of the M&I water returned to the stream at the selected load center, and can be either a positive or negative quantity, depending upon its source. In the case of the Meramec study, the return flow, Q_r , was a subtractive quantity since the Public Health Service assumed that the M&I waters in the upper basin came from underground water sources that were independent of stream flows, i.e., induction of flows from an outside water source independent of stream flows. The return flow was assumed constant for all three seasons, recognizing a time-lag aspect. Based on the above, the required stream needs, Q_o , were determined for each load center for the time periods involved in each analysis. Once these demands were established, they were converted from gpm to c.f.s. The Public Health Service then determined the amount of supplemental storage that would have to be furnished by the use of the formula $Q_o - Q_1 = \Delta_s$, where:

day. This gave a representation of the induced pollutant load that would have to be assimilated by the stream, assuming primary and secondary treatment in place. Projections were then made of the anticipated population growth in all parts of the basin on a time-phase basis. In conjunction with these population extrapolations, increased expected water use was also projected within the limits of the projections made by the U. S. Senate Select Committee. The product (population times water usage per capita) of these projections gave a basis for anticipated pollutant loads that were subsequently modified by anticipated mineral and organic pollutants to be anticipated from the industrial and rural aspects of the basin. To determine water quality requirements, the Public Health Service first determined the water supply (M&I) requirements and assumed that these demands were met and in place. The total water quality flow requirements (Q_t) were determined as the stream flow required to provide the necessary dilution to obtain a stream quality equal to 5 parts per million BOD. Its determination was based on the assumption that primary and secondary treatment had been provided the waste effluent at the discharge point or load centers. To determine the required stream flow (Q_o) necessary to meet the total flow requirements, the following formula was used: $Q_o = Q_t - Q_r$. Q_t was furnished on a seasonal basis, which recognized a temperature sensitive aspect, and was established in relation to water temperature. In the case of the Meramec Basin study, seasonal breakdowns were: a summer season of four months - June, July, August, and September; a spring and fall season of five months - March, April, May, October, and November; and a three-month winter season - December, January, and February. The return flow, Q_r , represents a portion of the M&I water returned to the stream at the selected load center, and can be either a positive or negative quantity, depending upon its source. In the case of the Meramec study, the return flow, Q_r , was a subtractive quantity since the Public Health Service assumed that the M&I waters in the upper basin came from underground water sources that were independent of stream flows, i.e., induction of flows from an outside water source independent of stream flows. The return flow was assumed constant for all three seasons, recognizing a time-lag aspect. Based on the above, the required stream needs, Q_o , were determined for each load center for the time periods involved in each analysis. Once these demands were established, they were converted from gpm to c.f.s. The Public Health Service then determined the amount of supplemental storage that would have to be furnished by the use of the formula $Q_o - Q_1 = \Delta_s$, where:

According to Mr. Rainwater, these flows are representative of the typical monthly distribution of annual uncontrolled runoff (see subparagraph 2b(3)(b)). Shown at the end of line 1 is the annual or yearly mean of the median flows. This was determined by summing the median monthly flows and dividing by 12. Line 2 shows the ratio of the individual monthly median flows to the annual or yearly mean of median monthly flows. Line 3 shows the annual flow at the Eureka, Missouri, gage that has a 5 percent probability of occurrence. This 5 percent probability flow was selected from an analysis by Public Health Service of the lower portion of a low-flow duration curve drawn for Eureka, Missouri, gage, and was equal to 1,320 c.f.s. for water quality. Line 4 represents the theoretical monthly flow having a 5 percent probability of occurrence (Q_5). This theoretical monthly flow was computed by multiplying the ratio shown in line 2 times the annual flow at Eureka for the corresponding probability. Shown in parentheses is a theoretical monthly flow for 2 percent probability (water supply). Accordingly, by use and definition, the Q_5 shown in line 4 for each month represents the uncontrolled stream flow that would occur 95 percent of the time (water quality) or 98 percent of the time (water supply) for the load center or reach of stream under consideration.

b. Part B. Shown in Part B are the computations used to determine supplemental storage required for water quality control in a reservoir located upstream from the reach studied. This annual requirement, referred to as "draft-on-storage," was computed by the formula $\Delta_s = Q_0 - Q_5$. Line 1 shows the monthly flow (Q_0), on a seasonal basis, needed to maintain a BOD stream requirement of 5 parts per million. Line 2 shows the theoretical flow requirements (Q_5) computed in Part A above. Line 3 shows the draft-on-storage for the climatic year. In this example, the stream theoretically required supplementation by reservoir for only three months during the climatic year. Total requirements equal 1,492 c.f.s. for three months in a year. Storage was computed as equal to 1,492, the monthly flow deficiency, times 30 days per month, times 2 acre-feet per c.f.s. or a total of 90,000 acre-feet supplemental storage required.

c. Part C. Shown in Part C are statistical data prepared by the St. Louis District, based on 42 years of record for the Eureka, Missouri, gage. The mean monthly discharges for each month in each year of record studied were arrayed in descending order of occurrence. Based on this information, curves were drawn and percent chance of occurrence on a probability basis was established. (See Table 2). Line 1 of Part C shows the average or mean monthly flow. Line 2 shows the median (50 percent) of the mean monthly flows. Line 3 shows the statistical monthly flow having a 95 percent chance of occurrence. Line 4 shows the statistical monthly flow having a 98 percent chance of occurrence.

d. Part D. Part D shows the effects on draft-on-storage required when utilizing the same stream flow requirements (Q_0), but a revised uncontrolled stream flow having 95 percent chance of occurrence from a statistical, rather than a theoretically computed, basis. Draft-on-storage required (Δ_s) is approximately twice that computed by the Rainwater method.

5. DISCUSSION OF RAINWATER METHOD

There are several aspects of the methodology that are questionable when applied to basin analysis and reservoir operation. These theoretical points are discussed briefly below.

a. Probability aspect. Mr. Rainwater's method purports to determine the present unregulated flow for each month that has a 95 percent chance of occurrence. It is claimed (see subparagraph 2b(3)) that the monthly median flow is characteristic of the annual flow distribution pattern of the stream, and by use of a ratio of medians, the annual flow for any degree of protection can be redistributed and converted into a monthly limit. Analysis has indicated that for a stream that has erratic flow characteristics, the use of medians is not applicable. It is felt, however, that the use of medians may be applicable when a stream is partially controlled or when a stream has very little year-round flow fluctuation. It should be stressed that the methodology is keyed to determine the unregulated flow having a 95 percent chance of occurrence for each month. Thus, it is apparent that the monthly, not the annual or yearly, flow pattern is the controlling element for determining draft-on-storage. It is suggested that in lieu of using the median approach, an analysis of each monthly flow should be made, similar to that undertaken by the St. Louis District office. A statistical analysis based on an array of occurring flows listed in descending order should be made and the monthly flow for the particular degree of protection desired be determined.

b. Length or duration of low-flow period. The Rainwater methodology determines only the amount of base or supplemental storage required for a climatic year. No attempt has been made to recognize an extended low-flow period similar to that experienced in the Meramec Basin for the period 1952 to 1957. Reference is made to Bulletin 51, State of Illinois Department of Registration and Education, entitled "Low Flows of Illinois Streams for Impounding Reservoir Design," published by the Illinois State Water Survey, 1964. The following information concerning low-flow series is contained in the publication:

"Past experience in analysing the 1952-55 drought in Illinois revealed that impounding reservoirs in Illinois are frequently under draft and drawdown for periods in excess of one year and may possibly be subject to drawdowns for as long as five years. For this reason it was necessary that the series of low flow events be selected in a manner not restricted to the annual fluctuations of runoff. A partial duration series of low flow events was selected as being most flexible and meaningful in this type of analysis. However, the partial series was selected only after intensive study, comparison, and evaluation of both the partial series and the more common and more easily interpreted annual series. . ."

The adequacy of storage (draft-on-storage) recommended in the Public Health Service report, dated February 1964, for water quality control only was analyzed by the St. Louis District office for the period of record 1922 to 1959, using the actual daily flows at the Eureka, Missouri, gage. Using the Public Health Service seasonal stream flow requirements (monthly Q_0), it was found that the 90,000 acre-feet of supplemental storage was insufficient to meet the demands at least 13 out of the 38 years of record studied. Analysis indicated that once the storage was depleted, the only available flow was inflow from the drainage area above the control point. However, the lengths of some of these low-flow periods were of such magnitude as to prevent complete reservoir refilling. Consequently, a succession of drought years prevented the reservoir from providing low-flow regulation 95 percent of the time.

c. Probability versus frequency of occurrence. It has been noted that the Public Health Service uses the expressions "95 percent chance of occurrence" and "5 percent probability" interchangeably. Use of the 95 percent chance of occurrence means that in application of a low-flow duration curve, the selected flow is equalled or exceeded 95 percent of the time for the period of record used. This does not necessarily have any relationship to a 5 percent probability or a flow that is equal to or less than that experienced once every 20 years.

d. Future stream depletion. As was brought out in subparagraph 2a(3)(b), analysis of regulated needs should be based on future depleted or modified stream flows (Q_1). The flow to be augmented in the future will not necessarily be the same flow measured now, but will be depleted by the then existing water use and management. The

Rainwater method, as used by the Public Health Service Regional Office, determined a typical monthly distribution of annual uncontrolled runoff (Q_1) and used it as a constant for all future time periods. As far as could be ascertained, the flow requirements Q_t , Q_r , and/or Q_o were not modified to reflect factors of future stream depletion. Consequently, storage requirements for future needs would not be sufficient when viewed from anticipated future stream depletion.

e. Data obsolescence. Allied to the problem of future stream depletion is data obsolescence (see subparagraph 2a(3)(a)). Reference is made to the open-file report prepared by the U. S. Geological Survey. This low-water study, covering the period 24 September through 1 October 1953, brought out the fact that the flows in the Big River were far above average for the basin due to the effect of waste being discharged into the stream from the then existing mining operations. Since then, mining operations have decreased and the use of historic data unmodified, as was done in relation to the Meramec Basin report by the Public Health Service, would provide insufficient amounts for water quality control.

f. Minimum control. The Rainwater methodology provides supplemental flow requirements to maintain a BOD count of 5 parts per million on an annual basis and monthly control. It is questionable whether supplementing flows having a 95 percent chance of occurrence are sufficient. Because of the extended low-flow periods now being experienced, it is suggested that a minimum flow limitation be provided. Assuming the Public Health Service criterion is to avoid criticism for providing excessive storage for augmentation, a minimum limit related to a safe BOD count, e.g., three parts per million, should be provided as a critical low with time (days) limitations if needed so that absolute stream regulation can be maintained. Knowing how long the lower BOD limit could be maintained without any serious complications to the public safety would be helpful in routing the demands against any mass curve modified to the critical load center under study.

g. Use of same base natural flow. Mr. Rainwater has maintained that his draft-on-storage is the amount of storage to be provided by the construction agencies. However, where there is a need for both water supply and water quality control in the same reach, he has analyzed these demands (Q_o) separately, utilizing the same natural flow as a base (Q_1) to compare his demands. As a result, storage requirements for the combined demands, as estimated by the Corps, are far greater than the sum of storage provided for both the individual demands when analyzed separately over the same natural base flow.

h. Degree of flow guaranteed. The Regional Office of the Public Health Service indicated that the selected flow (Q_i) representing the unregulated stream flow varied with the purpose under study. In the case of stream regulation for water quality control, a stream flow (Q_i) having a theoretical frequency of occurrence of 95 percent was used. In the case of water supply, the frequency of occurrence selected was 98 percent. Several questions have arisen in conjunction with this degree of flow:

(1) In a reach where both water supply and water quality control are required, which percent frequency of occurrence governs?

(2) Local interests have indicated a desire for guaranteed water supply, at least as pertains to the maximum deficiency during the period of record. Since water supply is a reimbursable cost, it is questioned as to why frequency of occurrence of less than the maximum deficiency of the period of record was selected.

6. VIEWS OF ST. LOUIS DISTRICT

Review of the Rainwater methodology used by the Public Health Service to determine supplemental needs and applicable values or benefits, for either water supply and/or water quality, has led to the following conclusions:

a. Use of the theoretically computed flow (Q_i) representing the unregulated stream flow results in a storage requirement (Δ_s) and time of need, which are erroneous when analyzed using historical stream flow data on an annual basis and converted to a monthly basis. The theoretically computed draft-on-storage or, in the case of water quality alternatives, the amount of pollutants that would have to be pumped over and above the amount that could be assimilated by the unregulated stream flow (Q_i), is computed for only a climatic year and is based on quantities of flows that are not applicable for streams that have erratic flow characteristics. Use of the climatic year does not recognize extended low-flow drought periods. Furthermore, the theoretically computed Q_i does not necessarily depict the flow pattern of the stream, instead, as in the case of the Meramec River Basin flow, incorrectly credits the streams with greater monthly flows and assimilation capabilities for the degree of protection desired and results in greatly reduced supplemental needs and resulting benefits.

b. Benefits computed based on either the annual draft-on-storage or pumped increments of sewage are inadequate when viewed from two other aspects. The first aspect is the discount factor used in relation to time of need. Use of a higher computed unregulated flow (Q_i) places the time of need and provision per purpose far later than historical stream flow data indicate. The second factor is that the reduced requirement, as determined by the methodology, may lead to selection of an alternative means as the basis for benefit evaluation that is wholly inadequate and impractical for obtaining the required degree of protection when correlated to historical flow data and extended flow durations.

c. In reaches of streams where two supplemental flows (water quality and water supply) are required, evaluation of supplemental storage or flow needs should be made on a total demand basis with storage allocations to individual purposes apportioned on a first added-last added basis. The resultant individual supplemental flow requirements would then serve as the basis for benefit evaluation. This automatically avoids the error of using the same natural flow when computing the individual needs for both purposes, as was done by the Public Health Service in the Meramec report.

d. In apportioning the supplemental flow requirements per purpose under first added-last added basis (see subparagraph c above), care should be exercised regarding the routings made to compare natural flows versus demands. In the case of water supply, the minimum flow of record should be selected as a base to which water supply needs are added under the first added basis. This would assure an analysis depicting a condition that would safeguard the existing riparian rights and avoid a complete stream depletion by withdrawals.

e. Selection of pumping increments of sewage from one basin to another is questionable as to practicality and feasibility in use as an alternative for water quality benefit evaluation. Legal problems may arise, but more important, a study would be required to develop future growth and pollution controls on both streams to determine whether this transfer of pollutants could be undertaken without just a transferring of one pollution problem from one basin to another.

f. Information obtained from the Public Health Service indicated that the following average temperatures for unregulated flows were used to define the seasonal breakdown for both water quality and water supply in the Meramec report: winter, 41°F; spring and fall, 59°F; summer 77°F. In its report dated February 1964, the

Public Health Service used the classic seasonal breakdown, i.e., a three-month winter period - December, January, and February; a three-month summer period - June, July, and August; and a six-month spring and fall period - March, April, May, September, October, and November. To determine the validity of this seasonal breakdown, an analysis by this District was undertaken using data obtained from the USGS Circular No. 216 entitled "Water Resources of the St. Louis Area, Missouri and Illinois," and water temperatures recorded at the water plant intake located on the Meramec River at Kirkwood, Missouri. A three-step analysis was made to define the seasonal breakdown. This analysis was based on first recognizing that the average temperature should be a true median point between the season's maximum and minimum temperatures; that the temperature differential for the maximum, average, and minimum in each season should be about the same; and that the range of the differential temperatures should be adjusted to reflect the effects of the appropriate season, i.e., the trend (recommended temperature ranges) would justify increasing or decreasing the flow requirements for water quality control. Results of this analysis were presented informally to the Public Health Service with the result that the definition of seasons on a monthly basis was changed and the revised monthly seasons were used in computing storage requirements and resulting benefits. However, with the increase in the number of low-flow periods that exceed a climatic year, it is felt that additional investigation and consideration should be given to further adjustment and refinement of the seasonal breakdown used by the Public Health Service since that agency equates water usage (M&I demands) and assimilation abilities (water quality requirements) to temperature aspects. This particular point becomes very important in determining supplemental flow requirements in a basin.

Prepared by
U. S. Army Engineer District,
St. Louis
11 August 1965



PUBLIC HEALTH SERVICE
WS & PC Program

DEPARTMENT OF HEALTH, EDUCATION, AND WELFARE

REGIONAL OFFICE

560 Westport Road
Kansas City, Missouri 64111

August 5, 1965

Colonel James B. Meanor, Jr.
District Engineer
St. Louis District
Corps of Engineers, U. S. Army
906 Olive Street
St. Louis, Missouri 63101

Re: LMSED-BM

Dear Colonel Meanor:

In accordance with Mr. Lawlor's letter of 30 July 1965, we submit the following background information concerning the need and benefit evaluations for water quality control in Reach M-7, the lower basin area of the Meramec River Basin in Missouri.

In estimating streamflow to be used in determining needs for water quality control, a 95 percent probability level was used instead of 90 percent, which is frequently used. This higher value was selected because of the expected complete urbanization of the area studied. Use of the 95% probability values increased the requirements.

The following table shows the expected population and quantity of sewage to be pumped.

Population and Sewage Pumped*

	<u>1970</u>	<u>2020</u>	<u>2070</u>
Population	130,000	620,000	2,000,000
Sewage Pumped MG/Year (Ave.)	100	3,000	8,000
Size of Pipelines	54"	66"	84"
Maximum Daily Pumpage Used in Design (MGD)	45	130	260

*Sewage to be pumped was estimated based on the monthly variation in the assimilating capacity of the unregulated flow (Q_1). The values in the report are the summation of all the incremental pumping requirements to handle the waste loadings which exceed the assimilative capacity of the unregulated flows established by a probability of occurrence. The critical flow is the low flow which will be exceeded 95 percent of the years.

Encl 2

Col. Meanor---8/5/65

In estimating the assimilating capacity of the stream in Reach M-7, the "Q₁", exceeded 95 percent of the time, was established by analysing all streamflow data of record using median monthly values on a climatic year basis. The return flow from upstream municipal ground water supplies will augment the streamflow and will be available for quality control in Reach M-7.

Estimated Unregulated Flow in 2070
That Will Be Exceeded 95 Percent of the Years

	<u>April</u>	<u>May</u>	<u>June</u>	<u>July</u>	<u>Aug</u>	<u>Sept</u>	<u>Oct</u>	<u>Nov</u>	<u>Dec</u>	<u>Jan</u>	<u>Feb</u>	<u>March</u>
MGD	962	893	609	442	405	381	256	337	381	497	562	1080

The pumping stations and pipelines were sized on the basis of need for each of the periods 1970, 2020, and 2070 to handle the maximum daily flows to be pumped. The following table is the summary of the capital, operating and maintenance costs, and their amortized value of the pumping stations and pipelines.

Pumping Stations and Pipeline Costs

Construction Cost \$	Year of First Need	Cost Discounted at 3% to 1970 \$	Annual Cost (1970 to 2070) Amortized @ 3% \$
6,800,000	1990	3,765,000	119,000
44,000*		736,000	23,300
8,500,000	2020	1,939,000	61,400
107,000*		628,000	20,000
11,000,000	2050	1,034,000	32,700
104,000*		145,000	4,600
		TOTAL	261,000


*Annual operation and maintenance costs from year of first need to end of study period.

Col. Meanor--8/5/65

The estimated cost of pumping stations and pipelines was found to be the most economical of the several most likely alternatives studied, and was, therefore, used as the benefit value.

We trust the above information will answer the question of the Board of Engineers for Rivers and Harbors, Washington, D.C.

Sincerely,


HERBERT C. CLARE, P.E.
Regional Program Director
Water Supply and Pollution Control

cc: DWSFC - Attn: Krause

Incl 3

Reformulation of #9 Irondale Reservoir

A. Pertinent data

	<u>Summary report</u>	<u>Revised</u>	<u>Difference</u>
Top dam elevation (m.s.l.)	887	884	3
Spillway crest elevation (ft)	860	855	5
Normal pool elevation (ft)	855	850	5
Minimum conservation pool (100-year sediment)	796	796	-
Storage (ac-ft)			
Total	161,000	140,000	21,000
Flood control	23,900	23,900	-
Joint-use	137,100	116,100	21,000
Sediment	5,800	5,800	-
Net joint-use	131,300	110,300	21,000
Pool areas (acres)			
Maximum spillway surcharge	8,000	7,500	500
Flood control pool	5,100	4,650	450
Normal pool	4,600	4,100	500
Minimum conservation pool	500	500	-
Dam dimensions			
Crest length (ft)	4,050	3,960	90
Base width (ft)	722	700	22
Volume (cubic yard)	1,273,000	1,171,000	102,000

Reformulation of #9 Irondale Reservoir (cont'd)

<u>B. Cost estimate</u>	<u>Summary Report</u>	<u>Revised</u>	<u>Difference</u>
01. Lands & damages	\$ 1,980,000	\$ 1,740,000	\$ -240,000
02. Relocations	3,831,000	3,180,000	-651,000
03. Reservoir	235,000	230,000	- 5,000
04. Dams	5,019,000	4,770,000	-249,000
06. Fish & wildlife facilities	11,000	10,000	- 1,000
08. Roads, railroads & bridges	367,000	370,000	3,000
14. Recreational facilities	537,000	400,000	-137,000
19. Buildings, grounds & utilities	233,000	220,000	- 13,000
20. Permanent operating equipment	164,000	160,000	- 4,000
30. Engineering & design	1,218,000	1,100,000	-118,000
31. Supervision & administration	805,000	720,000	- 85,000
Total	14,400,000	12,900,000	\$-1,500,000

C. Benefits

Flood control - total	\$ 63,400	\$ 63,400	\$ -
Meramec River	(63,400)	(63,400)	-
Mississippi River	-	-	-
Water quality	320,000	320,000	-
Water supply	9,400	7,600	- 1,800
Recreation - total	590,500	448,500	-142,000
General	(365,100)	(243,600)	(-121,500)
Fishing and hunting	(225,400)	(204,900)	(- 20,500)
Navigation	4,000	4,000	-
Total gross benefits	\$987,300	\$843,500	\$-143,800
Less negative benefits	800	800	-
Total net benefits	\$986,500	\$842,700	\$-143,800

D. Benefit-cost ratios

Annual economic cost -	\$627,500
Annual benefits -	\$842,700
Benefit-cost ratio -	1.3

Reformulation of #9 Irondale Reservoir (cont'd)

<u>E. Allocation of costs</u>	<u>Flood control</u>	<u>Water quality</u>	<u>Water supply</u>	<u>Total recreation</u>	<u>Navigation</u>	<u>Total</u>
Average annual benefits	63,400	320,000	7,600	448,500	4,000	843,500
Average annual charges (financial)	57,400	226,200	6,700	304,900	2,800	598,000
Benefit-cost ratio	1.1	1.4	1.1	1.5	1.4	1.4
Allocated first costs	1,399,000	5,470,000	138,000	5,824,000	69,000	12,900,000
Allocated O&M *	8,700	35,800	1,900	102,200	400	149,000

*Includes replacement costs.

Reformulation of #9 Irondale Reservoir (cont'd)

<u>F. Apportionment of costs</u> (costs in thousand dollars)	<u>First cost</u>	<u>O&M</u>
<u>Federal</u>		
Flood control		
Cost	1,399	8.7
Percent	10.84	5.84
Water quality		
Cost	5,470	35.8
Percent	42.40	24.03
Recreation		
Cost	4,133	61.2
Percent	32.04	41.07
Navigation		
Cost	69	0.4
Percent	0.54	0.27
Subtotal		
Cost	11,071	106.1
Percent	85.82	71.21
<u>Non-Federal</u>		
Water supply		
Cost	138	1.9
Percent	1.07	1.27
Recreation		
Cost	1,691	41.0
Percent	13.11	27.52
Subtotal		
Cost	1,829	42.9
Percent	14.18	28.79
<u>Total project costs</u>	12,900	149.0

Table 1
Water quality determination
PHS computations for draft on storage
(Reach M-7)

	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
4,394	3,267	2,472	1,260	949	769	819	1,245	1,616	2,262	2,480	4,351	25,884	
												12	= 2,157
2.04	1.51	1.15	0.58	0.44	0.36	0.38	0.57	0.75	1.05	1.15	2.02		
2,693 (2,240)	1,993 (1,661)	1,518 (1,155)	766 (638)	581 (484)	475 (396)	502 (418)	752 (627)	990 (825)	1,386 (1,153)	1,518 (1,263)	2,666 (2,222)		5% @ 1,320 c.f.s. (2% @ 1,100 c.f.s.)
487	487	1,410	1,410	1,410	487	487	487	200	200	200	380		
2,689	1,990	1,517	764	578	473	502	753	986	1,383	1,517	2,660		
(646+832+14=1,492)	x 30 (days per month)	x 2 (acre-ft. per c.f.s.)	= 90,000 acre-feet	- base storage for water quality - M-7									
5,882	5,403	4,129	2,111	1,132	1,094	1,417	1,972	2,224	2,979	3,264	4,840		
3,934	4,141	2,633	1,125	890	662	704	1,213	1,601	1,990	2,490	4,544		
1,110	925	675	475	396	390	428	510	585	562	650	950		
965	820	585	355	360	295	380	485	490	500	565	625		
487	487	1,410	1,410	1,410	487	487	487	200	200	200	380		
1,110	925	675	475	396	390	428	510	585	562	650	950		
		735	935	1,014	97	59	-	-	-	-	-		
			2,840 x 30 x 2 = 170,400	acre-feet									2,840

A. Based on Eureka Gage per PHS
Ave. 32 yrs. of record, to 1950 incl.
1. Median flows

2. Ratio = $\frac{\text{monthly median flow}}{\text{yearly mean of median monthly flows}}$
3. Annual flow @ Eureka having a 5% chance of occurrence or prob. (from duration curve)
4. Theoretical monthly flow having a 5% prob. of occurrence (step 2 x step 3) @ 2%

B. Computations for draft on storage
1. Demand, Q_0 (2,070)
2. Theoretical flow, 5% prob. (Q_1) (see A-4 above)
3. Draft on storage required (c.f.s.) (Δ_2) Storage

C. Corps of Engineers data (42 years of record, 1922-1963 incl.)
1. Mean monthly flows
2. Median of mean monthly flows
3. Monthly flow - 95% prob.
4. Monthly flow - 98% prob.

D. PHS demand vs Corps of Engineers 95% prob. flows
 Q_0
 Q_1
 Δ_2 (c.f.s.) storage

Table 2
 Statistical array
 Mean monthly discharges - April
 Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
22,600	1	2.38
20,000	2	4.76
15,500	3	7.14
15,400	4	9.52
12,770	5	11.90
12,390	6	14.29
9,060	7	16.67
8,551	8	19.05
8,044	9	21.43
7,513	10	23.81
7,390	11	26.19
7,178	12	28.57
6,770	13	30.95
6,387	14	33.33
5,880	15	35.72
4,705	16	38.10
4,650	17	40.48
4,363	18	42.86
4,330	19	45.24
4,138	20	47.62
3,934	21	50.00
3,901	22	52.38
3,883	23	54.76
3,737	24	57.14
3,663	25	59.52
3,568	26	61.91
3,381	27	64.29
3,370	28	66.67
3,357	29	69.05
2,953	30	71.43
2,790	31	73.81
2,750	32	76.19
2,675	33	78.57
2,388	34	80.95
2,350	35	83.34
2,126	36	85.72
2,102	37	88.10
1,798	38	90.48
1,700	39	92.86
1,100	40	95.24
969	41	97.62
945	42	100.00

Statistical array
Mean monthly discharges - May
Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
17,730	1	2.38
15,860	2	4.76
15,430	3	7.14
15,100	4	9.52
13,600	5	11.90
11,400	6	14.29
10,770	7	16.67
9,081	8	19.05
8,976	9	21.43
8,289	10	23.81
8,010	11	26.19
6,263	12	28.57
6,240	13	30.95
5,066	14	33.33
4,980	15	35.72
4,762	16	38.10
4,659	17	40.48
4,595	18	42.86
4,431	19	45.24
4,187	20	47.62
4,141	21	50.00
3,249	22	52.38
3,240	23	54.76
3,140	24	57.14
3,072	25	59.52
2,860	26	61.91
2,799	27 & 28	66.67
2,720	29	69.05
2,510	30	71.43
2,077	31	73.81
1,960	32	76.19
1,759	33	78.57
1,752	34	80.95
1,747	35	83.34
1,562	36	85.72
1,450	37	88.10
1,242	38	90.48
970	39	92.86
924	40	95.24
822	41	97.62
708	42	100.00

Statistical array
 Mean monthly discharges - June
 Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
18,070	1	2.38
16,000	2	4.76
14,800	3	7.14
13,890	4	9.52
11,490	5	11.90
8,350	6	14.29
7,940	7	16.67
7,539	8	19.05
7,188	9	21.43
4,880	10	23.81
4,800	11	26.19
4,241	12	28.57
3,580	13	30.95
3,433	14	33.33
3,394	15	35.72
3,230	16	38.10
3,199	17	40.48
3,110	18	42.86
2,874	19	45.24
2,830	20	47.62
2,633	21	50.00
2,145	22	52.38
1,952	23	54.76
1,836	24	57.14
1,800	25	59.52
1,776	26	61.91
1,522	27	64.29
1,470	28	66.67
1,420	29	69.05
1,405	30	71.43
1,338	31	73.81
1,260	32	76.19
1,020	33	78.56
943	34	80.95
922	35	83.34
914	36	85.72
849	37	88.10
820	38	90.48
803	39	92.86
673	40	95.24
590	41	97.62
503	42	100.00

Statistical array
 Mean monthly discharges - July
 Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
12,600	1	2.38
11,500	2	4.76
5,659	3	7.14
5,631	4	9.52
4,983	5	11.90
4,455	6	14.29
3,250	7	16.67
2,901	8	19.05
2,880	9	21.43
2,744	10	23.81
2,677	11	26.19
2,255	12	28.57
2,254	13	30.95
1,549	14	33.33
1,471	15	35.72
1,466	16	38.10
1,450	17	40.48
1,420	18	42.86
1,260	19	45.24
1,142	20	47.62
1,125	21	50.00
1,078	22	52.38
999	23	54.76
985	24	57.14
844	25	59.52
823	26	61.91
726	27	64.29
713	28	66.67
692	29	69.05
689	30	71.43
685	31	73.81
629	32	76.19
620	33	78.57
614	34	80.95
604	35	83.34
601	36	85.72
553	37	88.10
506	38	90.48
497	39	92.86
474	40	95.24
356	41	97.62
318	42	100.00

Statistical array
 Mean monthly discharges - August
 Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
4,286	1	2.38
4,175	2	4.76
2,780	3	7.14
2,120	4	9.52
2,062	5	11.90
1,855	6	14.29
1,710	7	16.67
1,640	8	19.05
1,510	9	21.43
1,474	10	23.81
1,200	11	26.19
1,077	12	28.57
1,073	13	30.95
1,061	14	33.33
1,056	15	35.72
1,051	16	38.10
1,045	17	40.48
1,024	18	42.86
949	19 & 20	47.62
890	21	50.00
820	22	52.38
772	23	54.76
771	24	57.14
758	25	59.52
733	26	61.91
729	27	64.29
654	28	66.67
648	29	69.05
612	30	71.43
554	31	73.81
551	32	76.19
544	33	78.57
526	34	80.95
510	35	83.34
488	36	85.72
473	37	88.10
428	38	90.48
407	39	92.86
396	40	95.24
386	41	97.62
255	42	100.00

Statistical array
 Mean monthly discharges - September
 Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
5,478	1	2.38
4,396	2	4.76
3,597	3	7.14
3,268	4	9.52
2,682	5	11.90
1,850	6	14.29
1,430	7	16.67
1,390	8	19.05
1,377	9	21.43
1,010	10	23.81
921	11	26.19
912	12	28.57
870	13	30.95
798	14 & 15	35.72
784	16	38.10
773	17	40.48
765	18	42.86
756	19	45.24
684	20	47.62
662	21	50.00
653	22	52.38
640	23	54.76
632	24	57.14
616	25	59.52
615	26	61.91
592	27	64.29
586	28	66.67
584	29	69.05
560	30	71.43
545	31	73.81
504	32	76.19
496	33	78.57
486	34	80.95
485	35	83.34
477	36	85.72
475	37	88.10
471	38	90.48
408	39	92.86
390	40	95.24
297	41	97.62
244	42	100.00

Statistical array
 Mean monthly discharges - October
 Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
12,120	1	2.38
3,850	2	4.76
3,760	3	7.14
3,600	4	9.52
3,019	5	11.90
2,820	6	14.29
2,620	7	16.67
2,407	8	19.05
1,740	9	21.43
1,600	10	23.81
1,231	11	26.19
1,149	12	28.57
1,120	13	30.95
1,062	14	33.33
1,031	15	35.72
1,014	16	38.10
847	17	40.48
791	18	42.86
717	19	45.24
705	20	47.62
704	21	50.00
689	22	52.38
684	23	54.76
675	24	57.14
653	25	59.52
638	26	61.91
622	27	64.29
592	28	66.67
589	29	69.05
578	30	71.43
575	31	73.81
573	32 & 33	78.57
571	34	80.95
569	35	83.34
548	36	85.72
504	37	88.10
438	38	90.48
436	39	92.86
427	40	95.24
418	41	97.62
239	42	100.00

Statistical array
Mean monthly discharges - November
Meramec River, Mo. - Eureka, Mo., gage .

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
7,317	1	2.38
7,086	2	4.76
5,790	3	7.14
5,209	4	9.52
5,070	5	11.90
4,660	6	14.29
4,507	7	16.67
3,830	8	19.05
3,390	9	21.43
2,312	10	23.81
1,973	11	26.19
1,943	12	28.57
1,932	13	30.95
1,930	14	33.33
1,822	15	35.72
1,638	16	38.10
1,569	17	40.48
1,382	18	42.86
1,278	19	45.24
1,224	20	47.62
1,213	21	50.00
1,212	22	52.38
1,140	23	54.76
939	24	57.14
927	25	59.52
913	26	61.91
882	27	64.29
865	28	66.67
829	29	69.05
821	30	71.43
786	31	73.81
686	32	76.19
644	33	78.57
641	34	80.95
632	35	83.34
630	36	85.72
629	37	88.10
587	38	90.48
511	39	92.86
510	40	95.24
486	41	97.62
464	42	100.00

Statistical array
Mean monthly discharges - December
Meramec River, Mo. - Eureka, Mo., gage .

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
9,296	1	2.38
7,250	2	4.76
5,380	3	7.14
4,436	4	9.52
3,954	5	11.90
3,782	6	14.29
3,730	7	16.67
3,660	8	19.05
3,550	9	21.43
3,400	10	23.81
3,340	11	26.19
3,280	12	28.57
3,012	13	30.95
2,360	14	33.33
2,240	15	35.72
2,145	16	38.10
1,917	17	40.48
1,811	18	42.86
1,700	19	45.24
1,630	20	47.62
1,601	21	50.00
1,506	22	52.38
1,469	23	54.76
1,340	24	57.14
1,255	25	59.52
1,250	26	61.91
1,167	27	64.29
1,164	28	66.67
1,125	29	69.05
1,100	30	71.43
991	31	73.81
870	32	76.19
826	33	78.57
805	34	80.95
791	35	83.34
711	36	85.72
690	37	88.10
670	38	90.48
650	39	92.86
581	40	95.24
511	41	97.62
426	42	100.00

Statistical array
Mean monthly discharges - January
Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
17,320	1	2.38
9,918	2	4.76
8,920	3	7.14
7,651	4	9.52
5,668	5	11.90
5,540	6	14.29
4,490	7	16.67
4,200	8	19.05
4,024	9	21.43
3,945	10	23.81
3,867	11	26.19
3,340	12	28.57
2,903	13	30.95
2,750	14	33.33
2,748	15	35.72
2,553	16	38.10
2,414	17	40.48
2,323	18	42.86
2,284	19	45.24
2,240	20	47.62
1,990	21	50.00
1,939	22	52.38
1,925	23	54.76
1,820	24	57.14
1,790	25	59.52
1,637	26	61.91
1,622	27	64.29
1,380	28	66.67
1,370	29	69.05
1,240	30	71.43
1,178	31	73.81
1,038	32	76.19
976	33	78.57
953	34	80.95
915	35	83.34
768	36	85.72
758	37	88.10
665	38	90.48
572	39	92.86
562	40	95.24
530	41	97.62
374	42	100.00

Statistical array
 Mean monthly discharges - February
 Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
10,350	1	2.38
8,428	2	4.76
8,251	3	7.14
7,090	4	9.52
6,588	5	11.90
6,529	6	14.29
6,380	7	16.67
6,232	8	19.05
4,810	9	21.43
4,310	10	23.81
4,210	11	26.19
4,149	12	28.57
3,951	13	30.95
3,850	14	33.33
3,840	15	35.72
3,186	16	38.10
3,060	17	40.48
2,652	18	42.86
2,610	19	45.24
2,532	20	47.62
2,490	21	50.00
2,470	22	52.38
2,309	23	54.76
2,280	24	57.14
2,065	25	59.52
2,023	26	61.91
1,949	27	64.29
1,948	28	66.67
1,847	29	69.05
1,750	30	71.43
1,523	31	73.81
1,453	32	76.19
1,390	33	78.57
1,256	34	80.95
1,143	35	83.34
1,120	36	85.72
1,117	37	88.10
1,107	38	90.48
1,100	39	92.86
620	40	95.24
569	41	97.62
538	42	100.00

Statistical array
 Mean monthly discharges - March
 Meramec River, Mo. - Eureka, Mo., gage

<u>Discharge</u> <u>c.f.s.</u>	<u>Occurrence</u>	<u>Percent</u> <u>occurrence</u>
13,390	1	2.38
9,949	2	4.76
9,855	3	7.14
7,797	4	9.52
7,330	5	11.90
7,320	6	14.29
7,233	7	16.67
7,224	8	19.05
7,082	9	21.43
6,960	10	23.81
6,910	11	26.19
6,739	12	28.57
6,706	13	30.95
6,624	14	33.33
6,467	15	35.72
6,250	16	38.10
5,591	17	40.48
4,757	18	42.86
4,715	19	45.24
4,550	20	47.62
4,544	21	50.00
4,520	22	52.38
4,182	23	54.76
4,054	24	57.14
4,030	25	59.52
3,647	26	61.91
3,354	27	64.29
3,120	28	66.67
3,071	29	69.05
3,060	30	71.43
3,007	31	73.81
2,815	32	76.19
2,580	33	78.57
2,270	34	80.95
2,253	35	83.34
2,194	36	85.72
1,900	37	88.10
1,570	38	90.48
1,516	39	92.86
949	40	95.24
671	41	97.62
514	42	100.00

Cost Allocation Studies

Irondale Reservoir

Determination of Separable Costs

A. Total Separable Cost

1. Flood Control (Normal Pool Area = 4,100 acres = 100%)

a. Separable cost = \$598,000 - \$552,700 = \$45,300

2. Water Quality

a. Separable cost = \$598,000 - \$548,200 = \$49,800

b. But without water quality, the normal pool is reduced to 3,600 acres or $\frac{500}{4,100} = 12\%$ and results in the following benefit loss: \$843,500 - \$470,500 = \$373,000, of which \$320,000 is water quality, \$3,900 is navigation, \$29,200 is general recreation and \$19,900 is Fish and Wildlife. Total recreation = \$49,100

c. Modified separable cost = \$49,800 - \$12% of \$62,500 (annual specific cost of recreation) or \$7,500) = \$42,300

3. Water Supply

a. Separable cost = \$598,000 - \$424,000 = \$174,000

b. But without water supply, the normal pool is reduced to 2,000 acres or $\frac{2,100}{4,100} = 51\%$ and results in the following benefit loss: \$843,500 - \$626,900 = \$216,600, of which \$7,600 is water supply, \$100 is navigation, \$124,200 is general recreation and \$84,700 is Fish and Wildlife. Total recreation = \$208,900

c. Modified separable cost = \$174,000 - (51% of \$62,500 (annual specific cost of reduction) or \$31,900) = \$142,100

B. Operation and Maintenance (including supervision and administration costs)

1. Flood Control

a. Separable cost = \$129,000 - \$123,000 = \$6,000

2. Water Quality

a. Separable cost = \$129,000 - \$116,000 = \$13,000

b. Modified separable cost = \$13,000 - (12% of \$34,000) =

\$8,900

3. Water Supply

a. Separable cost = \$129,000 - \$72,000 = \$57,000

b. Modified separable cost = \$57,000 - (51% of \$34,000) =

\$39,700

C. Replacement Costs

1. Flood Control

a. Separable cost = \$20,000 - \$19,000 = \$1,000

2. Water Quality

a. Separable cost = \$20,000 - \$18,000 = \$2,000

b. Modified separable cost = \$2,000 - (12% of \$7,000) =

\$1,200

3. Water Supply

a. Separable cost = \$20,000 - \$9,000 = \$11,000

b. Modified separable cost = \$11,000 - (51% of \$7,000) =

\$7,400

Project	Multiple-purpose project				Alternate single-purpose project				Alternate multiple-purpose projects			
	Specific costs		Joint-use costs	Total costs	Flood control	Water supply	Recreation	Flood control, water quality, water supply, recreation, and navigation	Flood control, water quality, water supply, recreation, and navigation	Flood control, water quality, water supply, recreation, and navigation	Flood control, water quality, water supply, recreation, and navigation	
	General	Specific										
1. Land and damages	100,000	-	1,750,000	1,850,000	335,000	419,000	1,520,000	1,440,000	1,440,000	1,440,000	1,440,000	
2. Navigation	-	-	3,300,000	3,300,000	1,381,000	1,443,000	3,300,000	3,300,000	3,300,000	3,300,000	3,300,000	
3. Recreation	-	-	3,375,000	3,375,000	805,000	220,000	257,000	257,000	257,000	257,000	257,000	
4. Other	-	-	5,695,000	5,695,000	6,697,000	4,352,000	5,420,000	5,420,000	5,420,000	5,420,000	5,420,000	
5. Fish and wildlife facilities	-	-	11,000	11,000	631,000	631,000	13,000	13,000	13,000	13,000	13,000	
6. Fish and wildlife facilities	-	-	642,000	642,000	631,000	631,000	443,000	443,000	443,000	443,000	443,000	
7. Fish and wildlife facilities	-	-	428,000	428,000	64,000	64,000	425,000	425,000	425,000	425,000	425,000	
8. Fish and wildlife facilities	-	-	283,000	283,000	97,000	97,000	314,000	314,000	314,000	314,000	314,000	
9. Fish and wildlife facilities	-	-	191,000	191,000	7,230,000	7,230,000	11,200,000	11,200,000	11,200,000	11,200,000	11,200,000	
10. Fish and wildlife facilities	-	-	13,270,000	13,270,000	7,780,000	7,780,000	7,900,000	7,900,000	7,900,000	7,900,000	7,900,000	
Total for project	610,000	12,000										
Investment												
Construction period (years)												
Construction during construction period	20,000	600	766,000	806,000	330,000	384,000	700,000	370,000	283,800	737,500	769,800	
Total investment	630,000	12,000	13,236,000	13,766,000	7,568,000	8,144,700	11,900,000	8,270,300	12,643,800	12,537,500	13,068,200	
Annual charges												
Interest & amortization	20,500	600	421,100	441,600	243,000	284,800	391,800	270,900	418,200	410,700	428,100	
Operation & maintenance	32,000	-	87,000	119,000	41,000	50,000	34,000	65,000	107,000	114,000	87,000	
Supervision & administration	2,000	-	6,000	16,000	1,500	1,800	1,200	6,000	8,000	8,000	8,000	
Replacement costs	7,000	-	13,000	26,000	1,000	2,000	3,000	12,000	18,000	15,000	13,000	
Total annual charges	62,500	600	535,100	598,000	206,000	328,800	436,800	351,900	548,200	537,700	538,100	
Benefits												
Flood control												
Water quality - local												
Water supply - local												
Water supply - State												
General recreation												
Fish & wildlife recreation												
Navigation												
Total annual benefits												

Cost allocation - 99 Irondele Reservoir
allocation by separable costs - remaining benefits method

Project purposes	Flood control	Water quality	Water supply	Total Recreation	General Recreation	Total fish & wildlife	Navigation	Total
Allocation of amount charges								
Benefits	63,400	320,000	7,600	446,500	243,600	204,900	4,000	843,500
Allocate costs	306,000	324,800	456,800	353,500	192,200	181,700	4,000	1,443,500
Benefits limited by alternate costs	63,400	320,000	7,600	353,500	192,200	181,700	4,000	744,500
Initial separable costs	43,300	320,000	-	62,900	62,500	400	-	104,200
Applicable benefits before dual costs	-	320,000	-	49,100	29,200	19,900	3,500	42,200
Applicable dual cost (water quality block storage)	-	36,200	7,600	3,500	3,200	2,300	400	42,200
Applicable benefits before dual costs	-	36,200	-	208,500	132,200	84,700	100	216,600
Allocated dual cost (water quality block storage)	-	36,200	7,600	137,000	81,500	35,500	100	142,100
Allocated dual cost (water supply block storage)	-	-	3,000	205,500	147,300	38,200	500	292,500
Total separable cost	43,300	36,200	2,400	148,400	44,500	103,200	2,500	436,200
Remaining benefits	18,100	283,700	2,200	99,400	29,100	69,200	2,500	385,400
Allocated residual cost	12,100	189,900	1,700	304,500	177,400	137,500	2,500	598,000
Total allocation of project cost	37,400	228,200	4,100	304,500	177,400	137,500	2,500	598,000
Benefit-cost ratio (financial)	1.1	1.4	1.1	1.3	1.4	1.6	1.4	1.4
Allocation of operation and maintenance including supervision & administration costs								
Initial separable costs	6,000	7,600	-	36,000	36,000	-	-	46,000
Allocated dual costs (water quality block)	-	7,600	-	1,200	700	300	100	8,500
Allocated dual costs (water supply block)	-	-	1,400	36,200	22,800	15,500	-	39,700
Total separable cost	6,000	7,600	1,400	37,200	57,500	16,000	100	88,600
Allocated residual cost	1,600	25,100	200	13,200	4,000	9,200	200	46,400
Total allocation	7,600	32,700	1,600	50,400	61,500	25,200	400	129,000
Allocation of replacement costs								
Initial separable costs	1,000	-	-	2,000	2,000	-	-	8,000
Allocated dual costs (water quality block)	-	1,000	-	200	100	100	-	1,200
Allocated dual costs (water supply block)	1,000	1,000	300	7,100	4,200	2,500	-	7,800
Total separable cost	2,000	2,100	300	9,300	6,300	3,600	-	16,000
Allocated residual cost	1,100	2,100	300	13,200	400	800	-	16,000
Total allocation	3,100	4,200	600	22,500	6,700	4,400	-	32,000
Allocation of investment								
Annual investment	46,700	190,400	4,800	202,700	104,200	99,500	2,400	449,000
Allocated investment	1,446,600	5,812,200	146,500	6,187,700	3,189,500	3,096,000	73,200	13,786,300
Allocation of construction expenditures								
Specific investment	1,486,600	5,812,200	146,500	649,400	656,600	12,600	23,200	649,400
Investment in joint-use facilities	87,500	341,900	8,000	383,400	248,500	124,100	4,200	13,074,900
Interest during construction on joint-use facilities	1,392,100	5,470,300	137,500	5,192,700	2,317,000	2,817,000	69,000	784,000
Construction expenditures in joint-use facilities	11,403	47,583	1,184	60,160	39,853	22,563	0,382	12,270,000
Percent of construction expenditures on joint-use facilities	-	-	-	630,000	618,000	12,600	69,000	630,000
Construction expenditures in specific facilities	1,392,100	5,470,300	137,500	5,192,700	2,317,000	2,817,000	69,000	12,270,000
Total construction expenditures	1,392,100	5,470,300	137,500	5,192,700	2,317,000	2,817,000	69,000	12,270,000
See								

Cost allocation - #9 Ironside Reservoir
allocation by separable costs - remaining benefits method

Project purposes	Flood Control	Water Quality	Water Supply	Total Recreation	General Recreation	Total Wildlife	Recreation	Total
Allocation of annual charges								
Benefits	63,400	320,000	7,600	446,500	263,600	304,900	4,000	643,500
Allocable costs	304,000	324,000	436,000	553,500	192,200	161,700	4,000	1,443,500
Benefits limited by alternate costs	63,400	320,000	7,600	553,500	192,200	161,700	4,000	1,443,500
Initial separable costs	45,300	320,000	-	62,900	62,900	400	-	108,500
Applicable benefits before dual costs	-	-	-	49,100	29,200	19,900	3,500	372,000
Applicable dual cost (water quality block storage)	-	-	-	5,500	3,500	2,300	400	42,300
Applicable dual cost (water supply block storage)	-	-	-	208,500	126,200	64,700	100	216,600
Allocable dual cost (water quality block storage)	-	-	-	137,000	81,500	55,500	100	142,100
Allocable dual cost (water supply block storage)	-	-	-	203,500	147,500	56,200	500	292,600
Total separable cost	45,300	36,300	5,000	203,500	147,500	56,200	500	436,300
Remaining benefits	18,100	283,700	2,600	149,000	44,900	103,500	2,500	305,400
Allocated residual cost	12,100	189,500	1,700	99,400	20,100	69,300	2,300	205,400
Total allocation of project cost	57,400	226,200	6,700	302,900	127,600	127,500	2,800	598,000
Benefit-cost ratio (financial)	1.1	1.6	1.1	1.3	1.4	1.6	1.4	1.4
Allocation of operation and maintenance including operation & administration costs								
Initial separable costs	6,000	7,600	-	36,000	36,000	-	-	46,000
Allocated dual costs (water quality block)	-	-	-	1,200	700	15,500	100	6,500
Allocated dual costs (water supply block)	-	-	-	36,500	22,800	15,500	-	26,700
Total separable cost	6,000	7,600	1,400	73,500	57,500	16,000	100	81,600
Allocated residual cost	1,600	25,100	200	13,200	4,000	9,200	200	49,400
Total allocation	7,600	32,700	1,600	86,700	61,500	25,200	400	129,000
Allocation of replacement costs								
Initial separable costs	1,000	1,000	-	7,000	7,000	-	-	8,000
Allocated dual costs (water quality block)	-	-	-	300	100	3,500	-	1,200
Allocated dual costs (water supply block)	-	-	-	16,200	11,200	3,000	-	2,600
Total separable cost	1,000	1,000	200	18,200	11,400	3,000	-	3,400
Allocated residual cost	1,100	2,100	300	13,500	11,700	2,800	-	2,600
Total allocation	2,100	3,100	500	31,700	23,100	5,800	-	6,000
Allocation of investment								
Annual investment	48,700	190,400	4,800	202,700	104,200	99,500	2,400	449,500
Allocated investment	1,486,600	5,812,200	146,500	6,187,700	3,180,500	3,004,800	73,200	12,704,500
Allocation of construction expenditures								
Specific investment	1,486,600	5,812,200	146,500	6,694,400	656,600	12,000	73,200	669,400
Investment in joint-use facilities	87,500	341,900	8,600	359,100	148,500	176,100	4,200	746,900
Interest during construction on joint-use facilities	1,399,100	5,470,300	137,900	5,193,700	2,375,800	2,817,500	69,000	12,270,000
Percent of construction expenditures on joint-use facilities	11.403	44.583	1.124	13.200	19.363	22.945	0.362	180.000
Construction expenditures in specific facilities	1,399,100	5,470,300	137,900	5,820,000	418,000	12,000	69,000	639,000
Total construction expenditures	1,399,100	5,470,300	137,900	5,820,000	2,993,800	2,829,500	69,000	12,900,000
Total	1,399,100	5,470,300	137,900	5,820,000	2,993,800	2,829,500	69,000	12,900,000

Cost Allocation Studies

Union Reservoir

Determination of Separable Costs

A. Total Separable Cost

1. Flood Control (Normal Pool Area = 6,500 acres = 100%)

a. Separable cost = \$1,189,200 - \$846,600 = \$342,600

2. Water Quality

a. Separable cost = \$1,189,200 - \$1,025,400 = \$163,800

b. But without water quality, the normal pool is reduced to 5,200 acres or $\frac{1,300}{6,500} = 20.0\%$ and results in the following benefit loss: \$1,835,800 - \$1,463,900 = \$371,900, of which \$177,700 is water quality, \$1,400 is navigation, \$144,600 is general recreation and \$48,200 is Fish and Wildlife. Total recreation = \$192,800

c. Modified separable cost = \$163,800 - (20.0% of \$176,900 (annual specific cost of recreation) or \$35,400) = \$128,400

3. Water Supply

a. Separable cost = \$1,189,200 - \$985,500 = \$203,700

b. But without water supply, the normal pool is reduced to 4,350 acres or $\frac{2,150}{6,500} = 33.1\%$ and results in the following benefit loss: \$1,835,800 - \$1,344,200 = \$491,600, of which \$172,100 is water supply, \$400 is navigation, \$239,300 is general recreation and \$79,800 is Fish and Wildlife. Total recreation = \$319,100

c. Modified separable cost = \$203,700 - (33.1% of \$176,900 (annual specific cost of recreation) or \$58,600) = \$145,100

B. Operation and Maintenance (including supervision and administration costs)

1. Flood Control

a. Separable cost = \$204,000 - \$175,000 = \$29,000

2. Water Quality

a. Separable cost = \$204,000 - \$174,000 = \$30,000

b. Modified separable cost = \$30,000 - (20.0% of \$103,100) =

\$9,400

3. Water Supply

a. Separable cost = \$204,000 - \$157,000 = \$47,000

b. Modified separable cost = \$47,000 - (33.1% of \$103,100) =

\$12,900

C. Replacement Costs

1. Flood Control

a. Separable cost = \$28,000 - \$20,000 = \$8,000

2. Water Quality

a. Separable cost = \$28,000 - \$23,000 = \$5,000

b. Modified separable cost = \$5,000 - (20.0% of \$13,000) =

\$2,400

3. Water Supply

a. Separable cost = \$28,000 - \$21,000 = \$7,000

b. Modified separable cost = \$7,000 - (33.1% of \$13,000) =

\$2,700

Summary of construction expenditures, annual financial charges and benefits (dollars)

Category	1954-1955			1955-1956			1956-1957			1957-1958			1958-1959			1959-1960			1960-1961			1961-1962			1962-1963			1963-1964			1964-1965			1965-1966			1966-1967			1967-1968			1968-1969			1969-1970			1970-1971			1971-1972			1972-1973			1973-1974			1974-1975			1975-1976			1976-1977			1977-1978			1978-1979			1979-1980			1980-1981			1981-1982			1982-1983			1983-1984			1984-1985			1985-1986			1986-1987			1987-1988			1988-1989			1989-1990			1990-1991			1991-1992			1992-1993			1993-1994			1994-1995			1995-1996			1996-1997			1997-1998			1998-1999			1999-2000			2000-2001			2001-2002			2002-2003			2003-2004			2004-2005			2005-2006			2006-2007			2007-2008			2008-2009			2009-2010			2010-2011			2011-2012			2012-2013			2013-2014			2014-2015			2015-2016			2016-2017			2017-2018			2018-2019			2019-2020			2020-2021			2021-2022			2022-2023			2023-2024			2024-2025			2025-2026			2026-2027			2027-2028			2028-2029			2029-2030			2030-2031			2031-2032			2032-2033			2033-2034			2034-2035			2035-2036			2036-2037			2037-2038			2038-2039			2039-2040			2040-2041			2041-2042			2042-2043			2043-2044			2044-2045			2045-2046			2046-2047			2047-2048			2048-2049			2049-2050			2050-2051			2051-2052			2052-2053			2053-2054			2054-2055			2055-2056			2056-2057			2057-2058			2058-2059			2059-2060			2060-2061			2061-2062			2062-2063			2063-2064			2064-2065			2065-2066			2066-2067			2067-2068			2068-2069			2069-2070			2070-2071			2071-2072			2072-2073			2073-2074			2074-2075			2075-2076			2076-2077			2077-2078			2078-2079			2079-2080			2080-2081			2081-2082			2082-2083			2083-2084			2084-2085			2085-2086			2086-2087			2087-2088			2088-2089			2089-2090			2090-2091			2091-2092			2092-2093			2093-2094			2094-2095			2095-2096			2096-2097			2097-2098			2098-2099			2099-2100			2100-2101			2101-2102			2102-2103			2103-2104			2104-2105			2105-2106			2106-2107			2107-2108			2108-2109			2109-2110			2110-2111			2111-2112			2112-2113			2113-2114			2114-2115			2115-2116			2116-2117			2117-2118			2118-2119			2119-2120			2120-2121			2121-2122			2122-2123			2123-2124			2124-2125			2125-2126			2126-2127			2127-2128			2128-2129			2129-2130			2130-2131			2131-2132			2132-2133			2133-2134			2134-2135			2135-2136			2136-2137			2137-2138			2138-2139			2139-2140			2140-2141			2141-2142			2142-2143			2143-2144			2144-2145			2145-2146			2146-2147			2147-2148			2148-2149			2149-2150			2150-2151			2151-2152			2152-2153			2153-2154			2154-2155			2155-2156			2156-2157			2157-2158			2158-2159			2159-2160			2160-2161			2161-2162			2162-2163			2163-2164			2164-2165			2165-2166			2166-2167			2167-2168			2168-2169			2169-2170			2170-2171			2171-2172			2172-2173			2173-2174			2174-2175			2175-2176			2176-2177			2177-2178			2178-2179			2179-2180			2180-2181			2181-2182			2182-2183			2183-2184			2184-2185			2185-2186			2186-2187			2187-2188			2188-2189			2189-2190			2190-2191			2191-2192			2192-2193			2193-2194			2194-2195			2195-2196			2196-2197			2197-2198			2198-2199			2199-2200			2200-2201			2201-2202			2202-2203			2203-2204			2204-2205			2205-2206			2206-2207			2207-2208			2208-2209			2209-2210			2210-2211			2211-2212			2212-2213			2213-2214			2214-2215			2215-2216			2216-2217			2217-2218			2218-2219			2219-2220			2220-2221			2221-2222			2222-2223			2223-2224			2224-2225			2225-2226			2226-2227			2227-2228			2228-2229			2229-2230			2230-2231			2231-2232			2232-2233			2233-2234			2234-2235			2235-2236			2236-2237			2237-2238			2238-2239			2239-2240			2240-2241			2241-2242			2242-2243			2243-2244			2244-2245			2245-2246			2246-2247			2247-2248			2248-2249			2249-2250			2250-2251			2251-2252			2252-2253			2253-2254			2254-2255			2255-2256			2256-2257			2257-2258			2258-2259			2259-2260			2260-2261			2261-2262			2262-2263			2263-2264			2264-2265			2265-2266			2266-2267			2267-2268			2268-2269			2269-2270			2270-2271			2271-2272			2272-2273			2273-2274			2274-2275			2275-2276			2276-2277			2277-2278			2278-2279			2279-2280			2280-2281			2281-2282			2282-2283			2283-2284			2284-2285			2285-2286			2286-2287			2287-2288			2288-2289			2289-2290			2290-2291			2291-2292			2292-2293			2293-2294			2294-2295			2295-2296			2296-2297			2297-2298			2298-2299			2299-2300			2300-2301			2301-2302			2302-2303			2303-2304			2304-2305			2305-2306			2306-2307			2307-2308			2308-2309			2309-2310			2310-2311			2311-2312			2312-2313			2313-2314			2314-2315			2315-2316			2316-2317			2317-2318			2318-2319			2319-2320			2320-2321			2321-2322			2322-2323			2323-2324			2324-2325			2325-2326			2326-2327			2327-2328			2328-2329			2329-2330			2330-2331			2331-2332			2332-2333			2333-2334			2334-2335			2335-2336			2336-2337			2337-2338			2338-2339			2339-2340			2340-2341			2341-2342			2342-2343			2343-2344			2344-2345			2345-2346			2346-2347			2347-2348			2348-2349			2349-2350			2350-2351			2351-2352			2352-2353			2353-2354			2354-2355			2355-2356			2356-2357			2357-2358			2358-2359			2359-2360			2360-2361			2361-2362			2362-2363			2363-2364			2364-2365			2365-2366			2366-2367			2367-2368			2368-2369			2369-2370			2370-2371			2371-2372			2372-2373			2373-2374			2374-2375			2375-2376			2376-2377			2377-2378			2378-2379			2379-2380			2380-2381			2381-2382			2382-2383			2383-2384			2384-2385			2385-2386			2386-2387			2387-2388			2388-2389			2389-2390			2390-2391			2391-2392			2392-2393			2393-2394			2394-2395			2395-2396			2396-2397			2397-2398			2398-2399			2399-2400			2400-2401			2401-2402			2402-2403			2403-2404			2404-2405			2405-2406			2406-2407			2407-2408			2408-2409			2409-2410			2410-2411			2411-2412			2412-2413			2413-2414			2414-2415			2415-2416			2416-2417			2417-2418			2418-2419			2419-2420			2420-2421			2421-2422			2422-2423			2423-2424			2424-2425			2425-2426			2426-2427			2427-2428			2428-2429			2429-2430			2430-2431			2431-2432			2432-2433			2433-2434			2434-2435			2435-2436			2436-2437			2437-2438			2438-2439			2439-2440			2440-2441			2441-2442			2442-2443			2443-2444			2444-2445			2445-2446			2446-2447			2447-2448			2448-2449			2449-2450			2450-2451			2451-2452			2452-2453			2453-2454			2454-2455			2455-2456			2456-2457			2457-2458			2458-2459			2459-2460			2460-2461			2461-2462			2462-2463			2463-2464			2464-2465			2465-2466			2466-2467			2467-2468			2468-2469			2469-2470			2470-2471			2471-2472			2472-2473			2473-2474			2474-2475			2475-2476			2476-2477			2477-2478			2478-2479			2479-2480			2480-2481			2481-2482			2482-2483			2483-2484			2484-2485			2485-2486			2486-2487			2487-2488			2488-2489			2489-2490			2490-2491			2491-2492			2492-2493			2493-2494			2494-2495			2495-2496			2496-2497			2497-2498			2498-2499			2499-2500			2500-2501			2501-2502			2502-2503			2503-2504			2504-2505			2505-2506			2506-2507			2507-2508			2508-2509			2509-2510			2510-2511			2511-2512			2512-2513			2513-2514			2514-2515			2515-2516			2516-2517			2517-2518			2518-2519			2519-2520			2520-2521			2521-2522			2522-2523			2523-2524			2524-2525			2525-2526			2526-2527			2527-2528			2528-2529			2529-2530			2530-2531			2531-2532			2532-2533			2533-2534			2534-2535			2535-2536			2536-2537			2537-2538			2538-2539			2539-2540			2540-2541			2541-2542			2542-2543			2543-2544			2544-2545			2545-2546			2546-2547			2547-2548			2548-2549			2549-2550			2550-2551			2551-2552			2552-2553			2553-2554			2554-2555			2555-2556			2556-2557			2557-2558			2558-2559			2559-2560			2560-2561			2561-2562			2562-2563			2563-2564			2564-2565			2565-2566			2566-2567			2567-2568			2568-2569			2569-2570			2570-2571			2571-2572			2572-2573			2573-2574			2574-2575			2575-2576			2576-2577			2577-2578			2578-2579			2579-2580			2580-2581			2581-2582			2582-2583			2583-2584			2584-2585			2585-2586			2586-2587			2587-2588			2588-2589			2589-2590			2590-2591			2591-2592			2592-2593			2593-2594			2594-2595			2595-2596			2596-2597			2597-2598			2598-2599			2599-2600			2600-2601			2601-2602			2602-2603			2603-2604			2604-2605			2605-2606			2606-2607			2607-2608			2608-2609			2609-2610			2610-2611			2611-2612			2612-2613			2613-2614			2614-2615			2615-2616			2616-2617			2617-2618			2618-2619			2619-2620			2620-2621			2621-2622			2622-2623			2623-2624			2624-2625			2625-2626			2626-2627			2627-2628			2628-2629			2629-2630			2630-2631			2631-2632			2632-2633			2633-2634			2634-2635			2635-2636			2636-2637			2637-2638			2638-2639			2639-2640			2640-2641			2641-2642			2642-2643			2643-2644			2644-2645			2645-2646			2646-2647			2647-2648			2648-2649			2649-2650			2650-2651			2651-2652			2652-2653			2653-2654			2654-2655			2655-2656			2656-2657			2657-2658			2658-2659			2659-2660			2660-2661			2661-2662			2662-2663			2663-2664			2664-2665			2665-2666			2666-2667			2667-2668			2668-2669			2669-2670			2670-2671			2671-2672			2672-2673			2673-2674			2674-2675			2675-2676			2676-2677			2677-2678			2678-2679			2679-2680			2680-2681			2681-26		
----------	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	-----------	--	--	---------	--	--

[illegible]

Cost Allocation Studies

Pine Ford Reservoir

Determination of Separable Costs

A. Total Separable Cost

1. Flood Control (Normal Pool Area = 3,700 acres = 100%)

a. Separable cost = \$1,171,900 - \$750,400 = \$421,500

2. Water Quality

a. Separable cost = \$1,171,900 - \$976,200 = \$195,700

b. But without water quality, the normal pool is reduced to 3,100 acres or $\frac{600}{3,700} = 16.2\%$ and results in the following benefit loss: \$1,840,200 - \$1,590,600 = \$249,600, of which \$74,200 is water quality, \$1,600 is navigation, \$142,000 is general recreation and \$31,800 is Fish and Wildlife. Total recreation = \$173,800

c. Modified separable cost = \$195,700 - (16.2% of \$211,000 (annual specific cost of recreation) or \$34,200) = \$161,500

3. Water Supply

a. Separable cost = \$1,171,900 - \$946,800 = \$225,100

b. But without water supply, the normal pool is reduced to 2,800 acres or $\frac{900}{3,700} = 24.3\%$ and results in the following benefit loss: \$1,840,200 - \$1,498,000 = \$342,200, of which \$81,400 is water supply, \$213,000 is general recreation and \$47,800 is Fish and Wildlife. Total recreation = \$260,800

c. Modified separable cost = \$225,100 - (24.3% of \$211,000 (annual specific cost of recreation) or \$51,300) = \$173,800

B. Operation and Maintenance (including supervision and administration costs)

1. Flood Control

a. Separable cost = \$223,000 - \$192,000 = \$31,000

2. Water Quality

a. Separable cost = \$223,000 - \$187,000 = \$36,000

b. Modified separable cost = \$36,000 - (16.2% of \$125,400) =

\$15,700

3. Water Supply

a. Separable cost = \$223,000 - \$176,000 = \$47,000

b. Modified separable cost = \$47,000 - (24.3% of \$125,400) =

\$16,500

C. Replacement Costs

1. Flood Control

a. Separable cost = \$30,000 - \$20,000 = \$10,000

2. Water Quality

a. Separable cost = \$30,000 - \$20,000 = \$10,000

b. Modified separable cost = \$10,000 - (16.2% of \$15,400) =

\$7,500

3. Water Supply

a. Separable cost = \$30,000 - \$19,000 = \$11,000

b. Modified separable cost = \$11,000 - (24.3% of \$15,400) =

\$7,300

Cost allocation - F2A Pine Ford Reservoir
allocation by separable costs - remaining benefits method

Project expenses	Flood control	Water supply	Water supply	Total recreation	General recreation	Total fish & wildlife	Navigation	Total
Allocation of annual charges								
Benefits	377,700	76,200	81,400	1,105,300	876,500	228,000	1,400	1,840,200
Allocated costs	679,300	475,500	425,000	704,200	558,400	-	1,400	1,437,100
Benefits limited by alternate costs	377,700	76,200	81,400	211,400	211,000	145,000	-	632,900
Initial separable costs	421,500	-	-	173,000	142,000	20,000	1,000	269,000
Applicable benefits before dual costs	-	76,200	-	112,500	91,900	20,000	-	161,500
Allocated dual cost (water quality block storage)	-	40,000	-	366,000	213,000	47,000	-	362,200
Applicable benefits before dual costs	-	-	-	132,500	108,000	28,000	-	173,800
Allocated dual cost (water supply block storage)	-	-	-	456,400	411,100	45,000	-	948,200
Applicable benefits before dual costs	-	-	-	287,000	167,300	180,500	-	470,900
Allocated dual cost (water supply block storage)	-	-	-	107,200	63,700	600	-	203,700
Initial separable cost	421,500	40,000	41,300	366,000	213,000	47,000	-	1,171,900
Remaining benefits	136,200	36,200	40,100	187,800	167,300	300	-	1,200
Allocated residual cost	17,300	17,300	17,300	365,600	478,000	88,000	-	1,171,900
Total allocation of project cost	440,100	39,500	58,600	563,400	686,300	125,800	-	1,223,100
Benefit-cost ratio (financial)	1.10	1.25	1.39	1.96	1.85	2.56	1.23	1.57
Allocation of operation and maintenance including supervision & administration costs								
Initial separable costs	31,000	-	-	125,400	125,400	-	-	156,400
Allocated dual costs (water quality block)	-	4,700	-	10,900	8,900	2,000	-	15,700
Allocated dual costs (water supply block)	-	-	3,900	12,600	10,300	2,300	-	18,500
Total separable cost	31,000	4,700	3,900	148,900	144,600	4,300	-	188,600
Allocated residual cost	11,400	1,900	2,900	18,100	16,800	7,200	-	39,400
Total allocation	42,400	6,600	6,800	167,000	161,400	11,500	-	223,000
Allocation of replacement costs								
Initial separable costs	5,900	-	-	15,400	13,400	-	-	21,300
Allocated dual costs (water quality block)	-	1,300	-	3,100	2,500	600	-	4,400
Allocated dual costs (water supply block)	-	-	1,000	2,300	2,700	600	-	4,300
Total separable cost	5,900	1,300	1,000	21,800	20,600	1,200	-	30,000
Allocated residual cost	-	-	-	-	-	-	-	-
Total allocation	5,900	1,300	1,000	21,800	20,600	1,200	-	30,000
Allocation of investment								
Initial investment	440,800	51,400	50,800	374,800	298,800	76,000	-	918,900
Allocated investment	13,455,700	1,569,000	1,550,700	11,641,000	9,121,100	2,319,500	33,400	26,050,000
Allocation of construction expenditures								
Specific investment								
Investment in joint-use facilities	13,455,700	1,569,000	1,550,700	2,134,900	2,143,100	13,800	-	2,156,900
Investment in joint-use facilities	791,500	92,300	91,200	9,284,100	6,978,000	2,306,100	33,600	25,893,100
Construction expenditures in joint-use facilities	12,664,200	1,676,700	1,459,500	8,738,000	6,567,500	2,170,500	31,400	24,370,000
Percent of construction expenditures in joint-use facilities	31.944	6.059	5.948	35.855	26.949	8.906	0.129	100.000
Construction expenditures in specific facilities	12,664,200	1,676,700	1,459,500	2,030,000	2,017,000	13,000	-	2,070,000
Total construction expenditures	12,664,000	1,677,000	1,459,000	10,768,000	8,584,500	2,183,500	31,600	26,400,000
Benefit-cost ratio (financial)	1.10	1.25	1.39	1.96	1.85	2.56	1.23	1.57

Cost Allocation Studies

Bourbeuse River Reservoir

Determination of Separable Costs

A. Total Separable Cost

1. Flood Control (Normal Pool Area = 850 acres = 100%)

a. Separable cost = \$352,200 - \$278,600 = \$73,600

2. Water Quality

a. Separable cost = \$352,200 - \$269,500 = \$82,700

b. But without water quality, the normal pool is reduced to 450 acres or $\frac{400}{850} = 47.1\%$ and results in the following benefit loss: \$478,900 - \$196,700 = \$282,200, of which \$175,700 is water quality, \$200 is navigation, \$88,900 is general recreation and \$17,400 is Fish and Wildlife. Total recreation = \$106,300

c. Modified separable cost = \$82,700 - (47.1% of \$60,900 (annual specific cost of recreation) or \$28,700) = \$54,000

B. Operation and Maintenance (including supervision and administration costs)

1. Flood Control

a. Separable cost = \$119,000 - \$98,000 = \$21,000

2. Water Quality

a. Separable cost = \$119,000 - \$79,000 = \$40,000

b. Modified separable cost = \$40,000 - (47.1% of \$34,900) =

\$23,600

C. Replacement Costs

1. Flood Control

a. Separable cost = $\$18,000 - \$12,000 = \$6,000 \times 0.71839^* =$
 $\$4,300$

2. Water Quality

a. Separable cost = $\$18,000 - \$4,000 = \$14,000$

b. Modified separable cost = $\$14,000 - (47.1\% \text{ of } \$5,500) =$
 $\$11,400 \times 0.71839^* = \$8,200$

* Adjustment factor

Summary of construction expenditures, annual financial charges and benefits (dollars)

[illegible]

[illegible]

Cost estimate
angler-use site
(boat access)

Federal

.14 Recreation facilities

Access road	\$1,000	
Comfort station	6,500	
Subtotal		7,500
Contingencies		<u>700</u>
Total recreation facilities		8,200

.30 Engineering & design		1,000
--------------------------	--	-------

.31 Supervision & administration		<u>800</u>
----------------------------------	--	------------

Total Federal cost		\$10,000
--------------------	--	----------

Non-Federal

.01 Lands	3,500	
-----------	-------	--

.14 Recreation facilities

Well w/pump	2,500	
Picnic tables	600	
Braziers	350	
Refuse containers	200	
Incinerator	350	
Subtotal		4,000
Contingencies		<u>700</u>
Total recreation facilities		4,700

Total lands and recreation facilities		8,200
---------------------------------------	--	-------

.30 Engineering & design		1,000
--------------------------	--	-------

.31 Supervision & administration		<u>800</u>
----------------------------------	--	------------

Total non-Federal cost		\$10,000
------------------------	--	----------

2.15

Cost estimate
angler-use site
(road access)

Federal

.14 Recreation facilities

Boat launching ramp	\$ 5,300	
Parking area, surface treatment	9,300	
Subtotal		14,600
Contingencies		<u>1,400</u>
Total recreation facilities		16,000

.30 Engineering & design 1,500

.31 Supervision & administration 1,000

Total Federal cost \$18,500

Non-Federal

.01 Lands \$ 3,500

.14 Recreation facilities

Well w/pump	2,500	
Comfort station	6,500	
Picnic tables	600	
Braziers	350	
Refuse containers	200	
Incinerator	350	
Road treatment	<u>1,000</u>	
Subtotal		11,500
Contingencies		<u>1,500</u>
Total recreation facilities		13,000

Total lands and recreation facilities 16,500

.30 Engineering & design 1,200

.31 Supervision & administration 800

Total non-Federal cost \$18,500



DEPARTMENT OF THE ARMY
CORPS OF ENGINEERS
BOARD OF ENGINEERS FOR RIVERS AND HARBORS
WASHINGTON, D.C. 20315

IN REPLY REFER TO

ENGBR

10 August 1965

SUBJECT: Meramec River, Missouri, Summary Report

THRU: Chief of Engineers
ATTN: ENGCW-PD
Department of the Army

TO: Division Engineer
U. S. Army Engineer Division, Lower Mississippi Valley
Vicksburg, Mississippi

1. Reference is made to BERH letter of 27 July 1965 on the subject report. Further review has indicated the need for additional information as discussed in the following paragraphs.

2. The Board staff has recently been advised informally by a representative of HEW, Washington, that the report prepared by the Kansas City, Missouri office of HEW, dated December 1964, and included on Summary Report, as Attachment 1, is recognized as HEW's "official report." Attachment 2 of the Corps Summary Report, indicates that data furnished by HEW were translated by the Corps into storage requirements prior to project formulation. It is stated that back-up data are on file in the St. Louis District office. Accordingly, it is requested that sufficient information be furnished for the Board to determine the method used in conversion of HEW's values to those given by the Corps in Attachment 2. For example, in HEW's report Table No. VIII-5, it is indicated that the supplemental flow above a base flow which would be required in connection with water quality control in reach M-7 during September in the year 2070, is estimated at 939 m.g.d. or 1,460 c.f.s. Attachment 2, Table 6 (Corps report) shows the water quality requirement for the same period (summer season), to be 1,880 c.f.s. or 420 c.f.s. greater. For the month of September in the year 2020, the HEW report gives a value equivalent to 216 c.f.s. as compared to 572.4 c.f.s. shown by the Corps Attachment 2. It is requested that the reasons

AIR MAIL

ENGBR

10 August 1965

SUBJECT: Meramec River, Missouri, Summary Report

and methods for these differences be clearly explained. Does HEW approve of the Corps changes in the method?

3. Attachment 5, Table 7, indicates that the value of reservoir storage allocated to evaporation increases rapidly in the later years of each reservoir project life. It is understood that the conservation pool elevation will generally stay the same throughout the project life of any one structure. It is not clear why the evaporation rate is less for the recreation use than for water supply and water quality control uses. Also, evaporation storage is less for 2020 needs than for 2045 needs as shown on Attachment 5, Table 8.

4. The Meramec Park project as proposed includes about 400,000 acre-feet of conservation storage including evaporation. Attachment 5, Table 8, indicates that if this project were constructed the water quality and water supply needs in sub-basin M-7 could be served adequately until after 2045. Based on current costs and unit benefit values, what would be the average annual benefits and benefit-cost ratios for each of the other projects if Union, Pine Ford, Irondale, and I-38 as proposed in the report were deferred for construction until the year 2020, assuming water supply and water quality storages for reach M-7 were maximized in the Meramec Park project first, and that needs for all purposes in the study remained constant after 2070.

5. Benefits for project purposes have been evaluated in many cases by using the least costly alternative single- or multiple-purpose reservoir which would most likely be constructed in the absence of the proposed project. The Secretary of Army's office has requested for similar reports that some development of alternatives for major structures be included in the report. It is suggested that specific cost data on the major alternatives used in deriving benefit values in the report be furnished for the information of the Board.

6. Benefits for water supply and water quality control are shown in Attachment 5, Table 9, as the summation of benefits for the local areas and for reach M-7. It is requested that information be furnished showing the breakdown between the local areas and reach M-7, for items of annual costs and annual benefits for the water supply and the water quality control features as they apply to each reservoir project recommended.

ENGBR

10 August 1965

SUBJECT: Meramec River, Missouri, Summary Report


7. There is inclosed a table showing allocated costs per acre-foot of storage for the primary purposes at each reservoir. Comments on the wide range in unit costs are invited.

8. It is not apparent from the summary report if consideration has been given to stage construction of reservoirs particularly with regard to the water quality and water supply storage requirements. Discussion of the value of stage construction would be appreciated.

9. Because of the heavy work load in ENGCW-PD, Planning and Reports at this time the Board staff has been delayed in discussing with that office certain policy matters which have developed in connection with the review of the report. It is anticipated that these matters will be discussed at an early date after which we will communicate further with your office. |||

10. Comments and revised pages, as appropriate, resulting from consideration of the foregoing would be appreciated at the earliest practicable date.

FOR THE BOARD:



EDMUND H. LANG
Colonel, Corps of Engineers
Resident Member

1 Incl
as

Copy furnished: (w/incl)
Dist Engr, St. Louis
Div Engr, LMVD (for advance information)

COMMENTS
ON
BERH LETTER, 10 AUGUST 1965
SUBJECT: MERAMEC RIVER, MISSOURI, SUMMARY REPORT

References below refer to paragraphs in subject letter.

a. Reference paragraph 2 - water quality Reach M-7. The Department of Health, Education, and Welfare report, Table VIII-5, shows the maximum reservoir release required over and above a computed theoretical unregulated stream flow (Q_i) to meet the needs for water quality in Reach M-7. These values are based on the Rainwater method of analysis, which involves the use of several formulas. First, the total stream flow (Q_t) required to provide the acceptable level of quality control is determined. The value of Q_t is given for seasonal periods and is based on the assumption that primary and secondary treatment is provided. Consideration is then given to the return flow (Q_r), which represents a portion of the municipal and industrial water returned to the stream at selected load centers. In the case of the Meramec Basin, this is a subtractive quantity since the source of the return flow comes from underground water and is independent of the stream flow. The required stream flow, as modified by return flow (Q_r), is then determined by the formula $Q_o = Q_t - Q_r$. The Public Health Service then determined the amount of supplemental storage release (s) by use of the formula $Q_o - Q_i = s$, where Q_o equals stream flow demands in terms of c. f. s.; Q_i a computed statistical flow in terms of c. f. s., characterizing the present unregulated stream flow at each load center; and s being the difference in terms of c. f. s. between Q_o and Q_i . The 939 m. g. d., which is s , shown for the month of September for the year 2070 in the Public Health Service report represents the reservoir release required for water quality in Reach M-7. By summing the monthly releases shown for 2070, the Public Health Service estimated the draft-on-storage required per year at 342,000 acre-feet. The 1,880 c. f. s. shown in Table 6, Attachment 2, of the Summary Report is the same stream flow demand (Q_o) as used by the Public Health Service. This figure was then compared by the District to the mass curve or daily flows (Q_i) for the Eureka gage to determine the amount of storage required to meet the 2070 demands over the critical periods of record. As indicated in Table 7, Attachment 2, of the

Summary Report, storage requirement for water quality only is estimated at 393,725 acre-feet to meet the 2070 needs in the lower basin area. The principal difference between the two storage values lies in the fact that the Public Health Service value for Q_i is based on a constant theoretical median monthly flow during a climatic year, whereas the Corps used actual flows over the actual periods of record. When adjusted to reflect concurrent demands for both water supply and water quality control and based on the first-added, last-added method of apportionment, 703,621 acre-feet of storage would be required for water quality in Reach M-7, as shown in Table 7 of Attachment 2. The Public Health Service, in using the Rainwater method, analyzed the needs for water supply and water quality control individually over the same theoretical base flow, without consideration of concurrent demands. It should be noted that no demand values are shown in the Public Health Service report; only the supplemental release (q_s) is given. Values used by the Corps were obtained from the regional office of the Public Health Service. The Public Health Service is in complete agreement that its values of draft-on-storage, as shown in its report, do not reflect the amount of storage required to meet current demands for both water supply and quality control. It is also in full agreement that final determination of the amount of storage to be recommended is the responsibility of the Corps.

b. Reference paragraph 3 - storage allocated to evaporation. Table 7, Attachment 5, of the Summary Report shows allocations of storage to the various purposes. Evaporation requirements, as listed, apply only to downstream low-flow augmentation. Evaporation requirements for recreation are not listed separately, but are included in the total storage for that purpose. Generally speaking, as low-flow augmentation increases on a time phase basis, evaporation requirements increase in relation to demand and time. An exception is the evaporation requirements for the year 2045, which are slightly less than the requirements for the year 2020 in those reservoirs augmenting Reach M-7 flows. While the demands for the year 2045 are greater and the critical period longer than for the year 2020 demands, the net effect of evaporation and rainfall is less than for 2020. The reason for this difference lies in the fact that the critical period for the year 2045 demands includes more early spring and late fall and winter months than the 2020 demands, resulting in lesser evaporation requirements.

c. Reference paragraph 4 - deferring construction of Union, Pine Ford, Irondale, and I-38 Reservoirs. A reanalysis was made assuming Meramec Park Reservoir constructed initially, with the remaining four reservoirs deferred until the year 2020. Meramec Park would be capable of serving adequately the water quality needs in Reach M-7 to the year 2045, and water supply needs until sometime thereafter. Average annual benefits for Meramec Park Reservoir are estimated at \$4,333,400, and average annual economic charges at \$2,074,200, with a benefit-cost ratio of 2 to 1. Benefits applicable to the remaining reservoirs, Union, Pine Ford, Irondale, and I-38, were reevaluated assuming construction and operation as of the year 2020. Benefits applicable to increments of water supply storage were based on a single-purpose reservoir other than Meramec Park as the least costly alternative and discounted to the base year, 2020. Water quality needs in the upper basin area were also revised to reflect change in initial needs and discounting factors. The benefit-cost ratios for the five reservoirs, based on the above analysis, are compared with the benefit-cost ratios contained in the Summary Report, as shown in the following tabulation:

<u>Reservoir</u>	<u>Summary Report</u>	<u>Reevaluation</u>
Meramec Park	1.9	2.1
Pine Ford	1.4	1.4
Irondale	1.4	1.5
Union	1.4	1.2
I-38	1.3	1.3

While Meramec Park, acting alone, can fulfill the needs in the lower basin area for water quality to the year 2045 and water supply for sometime thereafter, the reservoir would not provide needed flood reductions and water quality control in the upper basin area and only partial flood reductions in the lower basin area, and only a portion of the urgent demand for waterborne recreation would be satisfied. Deferring construction of Union, Pine Ford, Irondale, and I-38 Reservoirs would result in benefits foregone amounting to approximately \$4,500,000 annually, of which \$3,200,000 would be in the lower basin area and \$1,300,000 in the upper basin area. Details of this reanalysis are contained in inclosure 1.

d. Reference paragraph 5 - benefits based on least costly alternative. The costs of the most economical alternative means which would most likely be constructed in the absence of the proposed projects were used as a measure of benefits for water supply and water quality control. The value of benefits for water supply and water quality control was based on the cost of single-purpose reservoirs having sufficient storage capacity to meet the desired flow requirements for the purposes served. Meramec Park Reservoir site was used for the location of the single-purpose reservoirs since its unit cost per acre-foot of storage was found to be the least of all sites studied. Based on demands, construction increments of 25 years were used. These costs were then converted to an equivalent uniform annual value over a 100-year period of analysis and discounted to reflect the time differentials between the time of need and the base year. Specific cost data on these alternatives used in deriving benefit values are shown in inclosure 2.

e. Reference paragraph 6 - water supply and water quality control for local areas and Reach M-7. Information showing the breakdown by local areas (upper basin) and Reach M-7 (lower basin) for items of annual cost and annual benefits for water supply and water quality is contained in inclosure 3 for the reservoirs recommended. Only in Union Reservoir are there dual benefits that pertain to low-flow augmentation for water quality control. Releases for the lower basin also satisfy water quality requirements in local Reach B-4, located immediately downstream from the reservoir. Benefits applicable to the local reach are considered incidental. Meramec Park and Pine Ford Reservoirs both contain water quality for low-flow augmentation in the lower basin only. Reservoirs in the upper basin, Irondale and I-38, provide low-flow augmentation in the interest of water quality for the upper area only, and are not used for water quality augmentation in Reach M-7. Since water supply is required for only the lower basin, all costs and benefits applicable thereto in project formulation pertain only to the lower basin, Reach M-7.

f. Reference paragraph 7 - allocated costs per acre-foot of storage. The primary reasons for the wide range in allocated costs per acre-foot of storage were previously discussed in the inclosure to second indorsement, LMSED-B, 13 August 1965, to letter, ENGBR, Board of Engineers for Rivers and Harbors, 27 July 1965, subject:

Meramec River, Missouri, Summary Report. Essentially the differences in costs are due to the values based on the least costly alternatives from which the benefits are derived and discounting of values from the time that the needs are met. Particular reference is made to the value of \$1.57 per acre-foot of water supply storage in Irondale Reservoir. Recreation carries the entire cost of this storage to sometime after the year 2045, when it is converted to use for water supply. The cost of this storage becomes approximately \$72 an acre-foot when viewed in light of its dual purpose. Contract for the use of this storage for water supply would be based on a cost analysis at the time such storage is first used for that purpose. The amount of local participation for this reservoir is equivalent to approximately 23 percent of the total project cost, as compared to approximately 21 percent for Pine Ford and Union Reservoirs and 28 percent for Meramec Park Reservoir.

g. Reference paragraph 8 - stage construction. Consideration has been given to stage construction of reservoirs, with particular reference to the water quality and water supply storage requirements. In this determination, the initial stage was formulated to provide the maximum degree of flood control warranted; water quality to meet the needs to the year 2020 in the upper and lower basin areas; water supply to meet the needs in the lower basin to the year 2020; and recreation based on normal pool levels attainable through storage provided for water supply and water quality control. In the initial stage construction, consideration was given to appropriate design which would permit subsequent enlargement, with minimum modifications, to meet additional capacity requirements for the second 50-year period, and acquisition initially of all lands which would be needed to meet the ultimate project requirements. Second stage construction would require more costly relocations than if undertaken initially; extensive modification for spillway and appurtenant works; additional land acquisition to provide borrow area for embankment, since it is contemplated that embankment materials would be obtained from the reservoir area; and abandonment or removal of much of the recreational facilities constructed for the initial phase. While stage construction would result in reduced annual charges when discounted for the final 50 years, the total cost of the project would be substantially increased, and the benefits foregone, primarily for recreation, would more than offset these savings. Projects as formulated in the Summary Report are less costly when constructed

initially than when undertaken under stage construction. Furthermore, storage requirements to meet the second 50-year needs were found incrementally justified.

3 Incl

- 1. Pertinent data -
deferred construction**
- 2. Cost data -
major alternatives**
- 3. Pertinent data -
water supply & water
quality control**

**Economic Analysis Based on Deferred
Reservoir Construction**

A. Meramec Park Reservoir alone (1970 construction)

Benefits

1. Flood control	\$ 827,600
2. Water quality (M-7 only)	618,500
3. Water supply (M-7 only)	
Base (thru 2045)	661,200
Increment (2045-2070)	7,300
Total water supply benefits	668,500
4. Total recreation including fish & wildlife	2,197,100
5. Navigation	21,700
Total gross benefits	4,333,400
Average annual economic charge	\$2,074,200
Benefit-cost ratio	2.1 to 1

End 1

**Economic Analysis Based on Deferred
Reservoir Construction**

**B. Deferred construction of Pine Ford, Irondale, Union
and Bourbeuse River Reservoirs (2020 construction)**

	<u>#2A Pine Ford</u>	<u>#9 Irondale</u>	<u>#29 Union</u>	<u>I-38 Bourbeuse River</u>
Benefits				
1. Flood control	\$ 577,700	\$ 63,400	\$ 472,700	\$ 86,600
2. Water quality				
Local	-	307,900	22,100	180,900
M-7	-	-	-	-
3. Water supply (M-7 only)	60,900	92,500	135,000	-
4. Total recreation	1,105,300	448,500	1,008,200	216,400
5. Navigation	-	-	100	-
Total gross benefits	1,743,900	912,300	1,638,100	483,900
Average annual economic charge	\$1,283,800	\$627,500	\$1,311,600	\$365,900
Benefit-cost ratio	1.4	1.5	1.2	1.3

Detailed Cost Data of Major Alternatives used for Benefit Evaluation

A. Low-flow augmentation water quality control lower basin, Reach M-7

Line Item	1970 (1995 needs)		1995 (2020 needs)		2020 (2045 needs)		2045 (2070 needs)	
	Total storage @ 39,044 ac-ft	Pool surface @ 3,200 acres	Total storage @ 108,814 ac-ft	Pool surface @ 5,900 acres	Total storage @ 240,240 ac-ft	Pool surface @ 9,600 acres	Total storage @ 858,081 ac-ft	Pool surface @ 21,800 acres
1. Project first cost (\$)								
a. Lands & damages	2,240,000 *		1,590,000		2,550,000		5,740,000	
b. Relocations	1,320,000		1,340,000		3,434,000		7,082,000	
c. Reservoir	636,000		790,000		947,000		1,255,000	
d. Dam	8,506,000		9,130,000		9,816,000		11,291,000	
e. Fish & wildlife facilities	11,000		11,000		11,000		11,000	
f. Roads, railroads & bridges	175,000		175,000		175,000		175,000	
g. Buildings, grounds & utilities	52,000		52,000		52,000		52,000	
h. Permanent operating equipment	79,000		79,000		79,000		79,000	
i. Engineering & design	1,314,000		1,370,000		1,582,000		2,074,000	
j. Supervision & administration	847,000		900,000		1,127,000		1,541,000	
Total project cost	15,400,000		15,437,000		19,773,000		29,300,000	
See	15,500,000		15,400,000		19,800,000		29,300,000	
Increment of cost	15,500,000 *		15,400,000		19,800,000		29,300,000	
Increment of construction cost								
w/o future land statements	13,800,000		1,800,000		4,400,000		9,500,000	
2. Project annual charges for operation and maintenance (\$)								
a. Labor								
Resident Supt/Mechanic	9,000		9,000		9,000		11,000	
Tractor-operator (@ \$8,500/yr ea)	17,000		17,000		25,500		34,000	
Laborer (@ \$6,100/yr ea)	24,400		24,400		30,500		42,700	
Total	50,400		50,400		65,000		87,700	
See	50,000		50,000		65,000		88,000	
b. Maintenance (including supervision and administration costs)								
Seed, spray, etc.	800		1,200		-		-	
Fuel	800		1,000		1,500		2,500	
Maintenance of bldg, equip, etc.	1,000		2,000		2,500		4,000	
Maintenance of roads, shoreline	3,200		5,900		9,600		21,800	
Total	5,800		10,100		13,600		28,300	
See	6,000		10,000		14,000		28,000	
c. Replacement costs	1,000		1,000		2,000		3,000	
d. Total	57,000		61,000		81,000		119,000	
e. Incremental operation & maintenance costs	57,000		4,000		20,000		38,000	

* Reflects initial cost expenditures for securing options or interest in real estate sufficient to preclude development incompatible to the project on lands required for later staged development.

Detailed Cost Data of Major Alternatives used for Benefit Evaluation

B. Low-flow augmentation water supply lower basin, Reach M-7

Line Item	1970 (1995 needs)		1995 (2020 needs)		2020 (2045 needs)		2045 (2070 needs)	
	Total storage @ 36,544 ac-ft Pool surface @ 3,000 acres		Total storage @ 68,361 ac-ft Pool surface @ 4,000 acres		Total storage @ 108,417 ac-ft Pool surface @ 5,800 acres		Total storage @ 613,156 ac-ft Pool surface @ 12,600 acres	
1. Project first cost (\$)								
01. Lands & damages	1,652,000 *		1,077,000		1,528,000		3,368,000	
02. Relocations	1,320,000		1,330,000		1,340,000		5,022,000	
03. Reservoir	634,000		705,000		790,000		1,074,000	
04. Dam	8,496,000		8,778,000		9,117,000		10,422,000	
05. Fish & wildlife facilities	11,000		11,000		11,000		11,000	
06. Roads, railroads & bridges	175,000		175,000		175,000		175,000	
07. Buildings, grounds & utilities	52,000		52,000		52,000		52,000	
08. Permanent operating equipment	79,000		79,000		79,000		79,000	
09. Engineering & design	1,315,000		1,338,000		1,376,000		1,750,000	
10. Supervision & administration	846,000		872,000		903,000		1,300,000	
Total project cost	14,580,000		14,417,000		15,371,000		23,253,000	
Use	14,600,000 *		14,400,000		15,400,000		23,300,000	
Increment of cost								
Increment of construction cost w/o future land easements	13,800,000		600,000		1,000,000		7,900,000	
2. Project annual charges for operation and maintenance (\$)								
a. Labor								
Resident Supt/Mechanic	9,000		9,000		9,000		9,000	
Tractor-operator (@ \$0.500/yr ea)	17,000		17,000		17,000		25,500	
Laborer (@ \$6.100/yr ea)	24,400		24,400		24,400		30,500	
Total	50,400		50,400		50,400		65,000	
Use	50,000		50,000		50,000		65,000	
b. Maintenance (including supervision and administration costs)								
Seed, spray, etc.	800		1,100		1,200		2,000	
Fuel	800		900		1,000		3,000	
Maintenance of bldg, equip, etc.	1,000		1,900		2,000		12,600	
Maintenance of roads, shoreline	3,000		5,700		5,800		17,600	
Total	5,600		10,000		10,000		18,000	
Use	6,000		1,000		1,000		2,000	
c. Replacement costs	1,000		1,000		1,000		85,000	
d. Total	57,000		61,000		61,000		24,000	
e. Incremental operation & maintenance costs	57,000		4,000		-		-	

* Reflects initial cost expenditures for securing options or interest in real estate sufficient to preclude development incompatible to the project on lands required for later staged development.

**Annual Benefits and Costs for Water Quality and Water Supply
(dollars)**

<u>Reservoir</u>	<u>Water quality</u>		<u>Water supply</u>		<u>Total</u>
	<u>Upper basin (local)</u>	<u>Lower basin (M-7)</u>	<u>Upper basin (local)</u>	<u>Lower basin (M-7)</u>	
#2A Pine Ford					
Annual benefits	-	74,200	-	81,400	155,600
Annual costs (financial)	-	59,300	-	58,600	117,900
#9 Irondale					
Annual benefits	320,000	-	-	7,600	327,600
Annual costs (financial)	226,200	-	-	6,700	232,900
#17 Meramec Park					
Annual benefits	-	388,500	-	431,000	819,500
Annual costs (financial)	-	181,200	-	188,100	369,300
#29 Union					
Annual benefits	21,900	155,800	-	172,100	349,800
Annual costs (financial)	10,200	105,500	-	107,500	232,200
I-38 Bourbeuse River					
Annual benefits	175,700	-	-	-	175,700
Annual costs (financial)	132,900	-	-	-	132,900

Incl 3